

Todolist for PGFPlots

1.12.1

Christian Feuersänger

May 2, 2015

Contents

1	Release TODO	1
2	Tests	5
3	Documentation todo	5
4	Bugs/Features in PGF/TikZ	7
5	Bugs in PGFPlots	76
6	Feature Proposals PGFPlots	71

1 Release TODO

The following steps have to be done for every release:

- run tests against pgf CVS
- run tests against latest pgf stable
- finish manual
 - update the description for the `compat` key to the most recent version
 - update `pgfplots.preamble.tex` such that it contains `—compat=—newest`
 - fix warnings
 - browse through it
- ensure that the “compile” matrix (below this list) is complete for pgf CVS and the latest pgf Stable
- update ChangeLog with “RELEASED VERSION XXX” and update README
- assign git tag for new version

- run `scripts/pgfplots/pgfplotsrevisionfile.sh` to assign the package versions based on tag
- recompile manual (to pick up the correct version)
- run primitive example files
- run context tests (basically compile and browse-through. There are no assertions.)
 - run against pgf CVS
 - run against latest pgf stable
- adjust the release makefile to get correct file names
- assemble TDS.zip and CTAN.zip (using the release makefile)
 - `make -f pgfplots/scripts/pgfplots/Makefile.pgfplots_release_sourceforge` this creates the release files
 - make sure the archives do not contain wrong files.
- upload to CTAN.

```
Submitted to host
dante.ctan.org
Your name and email
    Christian Feuersnger <cfeuersaenger@users.sourceforge.net>
Filename
    pgfplots_1.6.1.ctan.flatdir.zip
Version number
    1.6.1
Location on CTAN
    /graphics/pgf/contrib/pgfplots/
Summary description
    pgfplots - Create normal/logarithmic plots in two and three dimensions for LaTeX.
License type
    gpl
Announcement text
...
Notes to maintainers
    As requested, I created a flat directory structure containing all files (i.e. it
```

- release to sourceforge. Make sure to update the README at top-level.
- upload to sourceforge web space (using the release makefile)
 - `make -f pgfplots/scripts/pgfplots/Makefile.pgfplots_release_sourceforge upload` this copies the manuals
 - change `Makefile.pgfplots_release_sourceforge` back to `unstable`
 - `make -f pgfplots/scripts/pgfplots/Makefile.pgfplots_release_sourceforge upload` this updates the unstable
 - if necessary, update `scp://cfeuersaenger,pgfplots@web.sourceforge.net/htdocs/index.php`
- send announcement to `pgfplots-features@lists.sourceforge.net`

2 Tests

last test verifications:

	pgf CVS	pgf 3.0.0	pgf 2.10	pgf 2.00	pgf 2.00+compat=default
regressiontests	for 1.12.1	for 1.12.1	for 1.12*	for 1.8 (7% fail)	2009-12-30
unittests	for 1.12*	for 1.12	for 1.12		
manual	for 1.12*	for 1.12	for 1.9	for 1.5	
pgfplotstable.pdf	for 1.12*	for 1.12	for 1.9	for 1.5	
example latex	for 1.12		for 1.9	2009-12-30	
example context(mkII)	for 1.12.1		for 1.9	2009-12-30	
example context(mkIV)		for 1.12.1	for 1.9	2009-12-30	
example plain tex	for 1.12		for 1.9	2009-12-30	
tests context (mkII)	for 1.12	for 1.12	for 1.9		
tests context (mkIV)		for 1.12*			

Note that context MK IV needs it installed in `~/texmf` (doesn't respect environment variables)

3 Documentation todo

pgfplotstodo.tex:132

Documentation Todo [open, Priority 5, Epic ‘']

Document standalone vs. external

- standalone does not work with loops (compare <http://tex.stackexchange.com/questions/191108/how-to-avoid-copied-code-with-the-combination-pgfplots-standalone>)
- generating just one single figure without a document is simpler with standalone
- ...

pgfplotstodo.tex:137

Documentation Todo [open, Priority 5, Epic ‘']

The new API for stacked plots + nodes near coords is missing, among it the normalized axis cs but see `\pgfplotspointgetnormalizedcoordinates`

pgfplotstodo.tex:172

Documentation Todo [open, Priority 5, Epic ‘']

document installation requirements when using lualatex (LUAINPUTS should contain pgfplots install dir)

- pgfplotstodo.tex:261 **Documentation Todo** [open, Priority 5, Epic ‘’]
bei dem Bsp-Tex zu pgfplotstable scheint eine Zeile im Tex-File zu fehlen:
`\usepackage{pgfplotstable}`
- Auerdem wre es zum Einstieg fr das aus der Datei lesen schn, wenn es zu den
Daten auch ein kurzes Beispiel-File fr einen Plot gbe.
- pgfplotstodo.tex:518 **Documentation Todo** [open, Priority 5, Epic ‘’]
try a bar plot with individually shaded bars
- FIXME : collect details
- pgfplotstodo.tex:534 **Documentation Todo** [open, Priority 5, Epic ‘’]
contour: a change label dist
- pgfplotstodo.tex:567 **Documentation Todo** [open, Priority 5, Epic ‘’]
document ‘execute at begin axis’ and its new variants
- pgfplotstodo.tex:572 **Documentation Todo** [open, Priority 5, Epic ‘’]
document how to plot against the coordindex
- pgfplotstodo.tex:585 **Documentation Todo** [open, Priority 5, Epic ‘’]
document how to identify the source of ”dimension too large” errors:
tracingstuff.
- pgfplotstodo.tex:600 **Documentation Todo** [open, Priority 5, Epic ‘’]
It seems as if the AMS command `$$\text{\ref{ref:to:a:plot}}$$`
instantiates the `\ref` at least four times. Document somehow that it is better
to use `\hbox` instead
- pgfplotstodo.tex:609 **Documentation Todo** [open, Priority 5, Epic ‘’]
clickable lib: I have the impression that acread fires warnings only for the
manual - not always when the clickable lib is used. Why!?

4 Bugs/Features in PGF/TikZ

pgfplotstodo.tex:633

pgfbug [open, Priority 5, Epic ‘]

topath in plots is broken since PGF 3.0.0: the following should be a single connected line (as it used to be for 2.10):

```
\documentclass{standalone}
\usepackage{tikz}

\begin{document}

  \begin{tikzpicture}
    \draw (-1,-1) -- (0,0)
      -- plot [id=x,domain=0.7:1.0] function {x};
  \end{tikzpicture}

\end{document}
```

pgfplotstodo.tex:637

pgfbug [open, Priority 5, Epic ‘]

external lib does not properly recompile unresolved references in external files, see <http://texwelt.de/wissen/fragen/7948/markierung-in-pgfplotlegende-fehlerhaft-ubernommen?Seite=1#7973>

pgfplotstodo.tex:673

pgfbug [open, Priority 5, Epic ‘]

When reading the manual v2.0 I found a typo 5.1 "Styling the nodes". Just after the first block of code, there is a sentence saying "... can achieve them. Once way is to use ..." which should be "One way is to use ..."

pgfplotstodo.tex:677

pgfbug [open, Priority 5, Epic ‘]

Beamer + pgf: the default template introduces a white line on top. Interestingly, it happens only for PGF CVS + beamer, but it appears to be dependent on third-party tools as well (see mail conversation with Stefan Tibus)

pgfplotstodo.tex:699

pgfbug [open, Priority 5, Epic ‘]

When using externalize function together with a transform canvas, the result is somehow cropped. See this example, compare output with deactivated and activated externalize.

```
\documentclass{article}
\usepackage{tikz}
\usetikzlibrary{external}
```

```

\tikzexternalize % activate!
\begin{document}
\begin{tikzpicture}[transform canvas={scale=0.7}]
\node {root}
child {node {left}}
child {node {right}}
child {node {child}}
child {node {child}}
};
\end{tikzpicture}
A simple image is \tikz \fill (1,0) circle(5pt);.
\end{document}

```

pgfplotstodo.tex:756

pgfbug [open, Priority 5, Epic ‘’]
pgf users Vol 50 issue 6:

Hi,

Thanks for TikZ. I'm trying to use the externalization library with the class file gOMS2e.cls, which is provided for the journal Optimization Methods and Software. The class file and related files/documentation can be found here:
<http://www.tandf.co.uk/journals/authors/gomslatex.zip>

My problem is that the externalized figures are shifted up and to the left significantly, cutting them off. This problem does not occur when not using externalization.

This seems to be related to the problem discussed here:

http://sourceforge.net/tracker/index.php?func=detail&aid=3037831&group_id=142562&atid=7527
and may also be related to this one:

http://sourceforge.net/mailarchive/forum.php?thread_name=4C0F342B.5040008%40ins.uni-bonn.d

In the other cases, the solution was to use \tikzifexternalizing for whatever conflicts with the externalization, but it seems that I can't do this when my class file is the offending bit. Is this true? I would really like to be able to use the correct \documentclass to generate the figures so that the size/fonts/etc. are consistent throughout the resulting document.

A minimal test example is included at the end of this message. It appears that the image is shifted ~1.25cm to the left and ~0.8cm up. The problem goes away when using \documentclass{article}.

I'm using the CVS version of pgf, and I get the same result when I produce postscript figures by using latex and setting

```

\tikzset{external/system call={
  latex \tikzexternalcheckshellescape -halt-on-error
-interaction=batchmode -jobname "\image" "\texsource";

```

```

dvips -o "\image".ps "\image".dvi}}

%-----
\documentclass[printer]{gOMS2e}
\usepackage{tikz}
\usetikzlibrary{external}
\tikzexternalize
\begin{document}
\begin{center}
\begin{tikzpicture}
\draw[step=.5cm] (-3,-3) grid (3,3);
\draw[blue,line width=2mm] (-0.5,-3) -- (-0.5,1.2) -- (3,1.2);
\end{tikzpicture}
\end{center}
\end{document}
%-----

```

Any help would be appreciated; I'm afraid it's over my head at this point.
Thanks!

pgfplotstodo.tex:795

pgfbug [open, Priority 5, Epic ‘']
some incompatibility

```

\documentclass{article}
\usepackage{german}
\usepackage[utf8]{inputenc} % erlaubt direkte Nutzung von Umlauten

\usepackage{pgfplots} % fuer plots

\usepackage{pgfplotstable} % fuer numeriktabellen
\usepackage{array,colortbl,booktabs}
\usetikzlibrary{external}
\tikzexternalize[force remake]

% DOESN'T WORK. Needs to disable externalization
\usepackage{vmargin}
\setpapersize{A4}
\setmarginsrb{2.5cm}{1cm}{2cm}{2cm}{8mm}{15mm}{5mm}{15mm}

\begin{document}
\begin{tikzpicture}
%\tracingmacros=2 \tracingcommands=2
\begin{axis}
\addplot {x};
\end{axis}
\end{tikzpicture}
\end{document}

```

pgfplotstodo.tex:816 **pgfbug** [open, Priority 5, Epic ‘’]
external bug:

```
\documentclass[
  pagesize=auto,                % 1
]{scrbook}
\usepackage{tikz}
\usetikzlibrary{external}
\tikzexternalize
\begin{document}
  \KOMAOption{twoside}{semi} % 2
  test
  \tikz \draw (0,0) circle (3pt);
\end{document}
```

pgfplotstodo.tex:823 **pgfbug** [open, Priority 5, Epic ‘’]
consider a matrix style which applies only to the outer matrix node style (see
feature request
https://sourceforge.net/tracker/?func=detail&atid=1060657&aid=3019259&group_id=224188
)

pgfplotstodo.tex:827 **pgfbug** [open, Priority 5, Epic ‘’]
make assignments to `\pgf@x` and `\pgf@y` always `\global`

pgfplotstodo.tex:831 **pgfbug** [open, Priority 5, Epic ‘’]
implement `\pgfmathfloattocount`

pgfplotstodo.tex:885 **pgfbug** [open, Priority 5, Epic ‘’]
the fpu can't be used inside of paths. That should be fixed. ~> the problem is
that paths may use `\pgfmath...` routines directly. ~> this should work! At
least with the public math macros `\pgfmathadd`. The `\pgfmathadd@` might be
implemented differently.

pgfplotstodo.tex:938 **pgfbug** [open, Priority 5, Epic ‘’]
active `'|'` characters result in compilation bugs (`\usepackage{program}`)

pgfplotstodo.tex:942 **pgfbug** [open, Priority 5, Epic ‘’]
`'text height=1em'` realisieren mit `[node font units]1em`

5 Bugs in PGFPlots

pgfplotstodo.tex:1014

Bug [open, Priority 10, Epic ‘] fill between fails to work with PGF 2.10

work-around: use the following patch

```
\documentclass[10pt]{beamer}
\usepackage{tikz}
\usepackage{pgf}
\usepackage{pgfplots}
\usepgfplotslibrary{fillbetween}

\makeatletter
\def\tikz@intersect@addto@path@names#1#2{%
  \edef\tikz@marshal{#2\expandafter\noexpand\csname tikz@intersect@path@name@#1\endcsname}
  \expandafter\expandafter\expandafter\def\expandafter\expandafter\expandafter\tikz@marshal
  \expandafter\expandafter\expandafter{\expandafter\tikz@marshal\expandafter{\tikz@inter
  \expandafter\pgfutil@g@addto@macro\expandafter\tikz@intersect@namedpaths\expandafter{\ti
}
\pgfkeys{%
  /tikz/name path global/.code={%
\expandafter\global\expandafter\let\csname tikz@intersect@path@name@#1\endcsname=\relax
  \tikz@key@name@path@new{#1}{\gdef}%
  },
  /tikz/name path local/.code={%
  \pgfkeys{/tikz/name path={#1}}%
  },
  /tikz/name path/.code={%
  \tikz@key@name@path@new{#1}{\def}%
  },
}
\makeatother

\begin{document}
\begin{frame}

\begin{tikzpicture}
\begin{axis}[%
axis x line*=bottom,
ymin=0,
ymax=1,
]

\addplot[name path=h,domain=-0.01:1,blue,line width=2pt] {5.5*x^4 - 8.4*x^3 + 3.2*x^2 + 0.
\path[name path=axis] (axis cs:0,0) -- (axis cs:1,0);
```

```

\only<2->{
\addplot [fill=green, fill opacity=0.2]
    fill between[of=h and axis, soft clip={domain=0.0:0.4}];
}

\end{axis}
\end{tikzpicture}
\end{frame}
\end{document}

```

pgfplotstodo.tex:1054

Bug [open, Priority 9, Epic ‘’]

lualatex bug: table with $y=\backslash\text{coordindex}$ does not work

<http://tex.stackexchange.com/questions/227700/xbar-plots-in-pgfplots-1-12-gives-empty-y-axis-range-warning/227856#227856>

pgfplotstodo.tex:1658

Bug [open, Priority 8, Epic ‘’]

stacked plots seem to fail if there are negative axis limits...!?

see <http://tex.stackexchange.com/questions/196366/stacked-bar-plot-with-explicit-axis-domain>

It works as soon as one adds `disabledatascaling`

pgfplotstodo.tex:1078

Bug [open, Priority 5, Epic ‘substitute axis cs’]

substitute axis cs fails with `smithcharts`:

```

\documentclass{standalone}

\usepackage{pgfplots}
\usepgfplotslibrary{smithchart}

\pgfplotsset{compat=newest}

\begin{document}
  \begin{tikzpicture}
    \begin{smithchart}
      % \pgfplotsset{is smithchart cs}
      % \begin{scope}[/pgfplots/is smithchart cs]
        \draw [black!40,dashed] (0,0) arc (0:360:.5);
      % \end{scope}
    \end{smithchart}
  \end{tikzpicture}

```

```
\end{document}
```

pgfplotsstodo.tex:1110

Bug [open, Priority 5, Epic ‘substitute axis cs’]
substitute axis cs fails to work with ++ (0,1cm) (probably for ++ everytime)

workaround: use ++ (0cm,1cm) or compat=1.10.

```
\documentclass{article}
\usepackage{pgfplots}
\begin{document}
```

```
\pgfplotsset{compat=1.9}
\begin{tikzpicture}
\begin{axis}[
xmin=-1,xmax=1,
ymin=-1,ymax=1
]
\draw (axis cs:0,0) -- ++(0,1cm);
\end{axis}
\end{tikzpicture}
```

```
\pgfplotsset{compat=1.12}
\begin{tikzpicture}
\begin{axis}[
xmin=-1,xmax=1,
ymin=-1,ymax=1
]
\draw (axis cs:0,0) -- ++(0,1cm);
\end{axis}
\end{tikzpicture}
\end{document}
```

pgfplotsstodo.tex:1183

Bug [open, Priority 5, Epic ‘’]
error bars + fill between do not work together (per email of Jerzy Wrobel Jan 28, 2015):

```
\documentclass[12pt,border=8pt]{standalone}
\usepackage[utf8]{inputenc}
\usepackage{mathtools}
\usepackage{pgfplots}
\usepackage[T1]{fontenc}
\usepackage{fouriernc}
\pgfplotsset
{
```

```

compat=newest,
every axis/.append style={line width=0.03cm,axis line style={line width=0.02cm}},
every tick/.append style={line width=0.02cm,color=black},
every axis label/.append style={font=\small},
tick label style={font=\small},
legend style={font=\small,draw=none},
title style={font=\small},
axis on top=false,
table/col sep=comma
}
\tikzset
{
every pin/.style={font=\small},
}
\pgfkeys{/pgf/number format/set thousands separator = }
\usepgfplotslibrary{fillbetween}
\usetikzlibrary{patterns}
\begin{document}
\begin{tikzpicture}
\begin{axis}
[
width=70mm,
height=70mm,
axis x line=box,
axis y line=box,
scale only axis,
enlarge x limits=true,
enlarge y limits=true,
grid=none,
xlabel=wave length (microns),
ylabel=Experiment1916 (a.u.),
extra y ticks={0},
extra y tick labels={},
extra y tick style={grid=major,major grid style={line width=0.02cm,color=black,densely das
}
\addplot+
[
name path=1,
line join=round,
every mark/.append style={solid,fill opacity=1.0},
mark repeat=1,
mark phase=1,
error bars/.cd,
y dir=both,
y fixed=10,
]
table
[
skip first n=4,
x index=0,

```

```

y index=1,
]
{Coblentz1919.csv}
;
\path[name path=B] (0.4,0) -- (0.75,0);
\addplot[pattern=north west lines,forget plot] fill between[of=1 and B];
\end{axis}
\end{tikzpicture}
\end{document}

```

pgfplotstodo.tex:1189 **Bug** [open, Priority 5, Epic “]

bugs:#74 Wrong value from the \pgfplotsunit[xyz]length macro

<https://sourceforge.net/p/pgfplots/bugs/74/>

pgfplotstodo.tex:1195 **Bug** [open, Priority 5, Epic “]

bugs:#75 \pgfplotstablesort doesn't sort correctly if there's a NaN in the

column

<https://sourceforge.net/p/pgfplots/bugs/75/>

pgfplotstodo.tex:1201 **Bug** [open, Priority 5, Epic “]

|(axiscs:0,0)— is not the same as (axis cs:0,0,0) in 3d axes! something

with the datascale trafo spoils it

<http://tex.stackexchange.com/questions/223623/pgfplots-tikz-interoperability-and-axis-equal>

pgfplotstodo.tex:1305 **Bug** [open, Priority 5, Epic “]

spurious shifts /displacement when using group plots and and discontinuities:

<http://tex.stackexchange.com/questions/183399/wrong-placement-and-or-size-of-picture-plot-with-groupplot-of-table-and>

pgfplotstodo.tex:1310 **Bug** [open, Priority 5, Epic “]

get rid of this boolean “apply@datatrafo@”. It is a synonym for “is linear”. I

would even say: apply the trafo to log axes as well, perhaps with no-op

configuration

pgfplotstodo.tex:1326

Bug [open, Priority 5, Epic ‘]

fillbetween fails to work inside of groupplots:

<http://tex.stackexchange.com/questions/207450/fillbetween-from-pgfplots-does-not-work-inside-groupplots>

Duplicate of the problem with cell pictures

<http://tex.stackexchange.com/questions/227775/pgfplot-image-messed-up-with-newer-texlive>

pgfplotstodo.tex:1413

Bug [open, Priority 5, Epic ‘]

set layers fails to work with colorbars. In fact, it is just `cell picture=false`, somewhere in `pgfplots@BEGIN@cell@picture@DISABLED`.

I have experimented with a patch (see `~/tmp/cellpicturefalse.diff`)

```
\documentclass{standalone}
\usepackage{pgfplots}
\pgfplotsset{width=7cm,compat=1.11}
\begin{document}
  \begin{tikzpicture}
    \node[fill=red] (XYZ) at (40pt,40pt) {.};
    \draw[red,->](0cm,0cm) -- (XYZ);

    \pgfplotsset{cell picture=false}
    %\tracingmacros=2 \tracingcommands=2
    \begin{axis}[
      clip=false,
      name=axisA,
      at={(XYZ)},
    ]
      \addplot[contour prepared]
        table {
          2 2 0.8
          0.857143 2 0.6
          1 1 0.6
          2 0.857143 0.6
          2.5 1 0.6
          2.66667 2 0.6
          0.571429 2 0.4
          0.666667 1 0.4
          1 0.666667 0.4
          2 0.571429 0.4
          3 0.8 0.4
          0.285714 2 0.2
          0.333333 1 0.2
        }
    \end{axis}
  \end{tikzpicture}
\end{document}
```

```

        1 0.333333 0.2
        2 0.285714 0.2
        3 0.4 0.2
    };
\end{axis}

%\begin{axis}[at={(axisA.north east)},anchor=north west]
%\addplot {x};
%\end{axis}
\node at (current axis.right of north east) {x};
\end{tikzpicture}
\end{document}

```

another manifestation of this problem:

```

\documentclass{standalone}
\usepackage{pgfplots}
\begin{document}
\begin{tikzpicture}
\pgfplotsset{
compat=1.11,
samples=2,
set layers, cell picture=false,
}
\begin{axis}[
scale only axis,
xlabel=x,ylabel=y,
axis y line*=left,
xmin=-1,
xmax=1,
ymin=-1, ymax=1,
%enlargelimits=true,
]
\addplot {x};
\end{axis}
\begin{axis}[
scale only axis,
xlabel=x,ylabel=y,
axis y line*=right,
xmin=-1,
xmax=1,
ymin=0, ymax=2,
%enlargelimits=true,
]
\addplot {1-x};
\end{axis}
\end{tikzpicture}
\end{document}

```

pgfplotstodo.tex:1447

Bug [open, Priority 5, Epic ‘]

REGRESSION:

```
\documentclass{article}
\usepackage{pgfplots}

\pgfplotsset{compat=newest}

\begin{document}
\begin{tikzpicture}
\begin{axis}[ybar,
symbolic x coords={foo,bar,baz},
x=2cm,
enlarge x limits={abs=bar}, xtick=data,
]
\addplot coordinates { (foo,1) (bar,3) (baz,2) };
\end{axis}
\end{tikzpicture}
\end{document}
```

broke sometime between 1.6 (OK) and 1.7 (compile error).

pgfplotstodo.tex:1525

Bug [open, Priority 5, Epic ‘]

combination of dateplot and x tick label as interval does not work well together:

- one can only format one of the dates
- the description applies to the *right* end rather than the left end

[see [bugtracker/minimal_0.pdf](#)]

```
\documentclass{standalone}
\usepackage{pgfplots}
\pgfplotsset{compat=newest}
\usepgfplotslibrary{dateplot}
\begin{document}
\begin{tikzpicture}
\begin{axis}[
const plot, % unrelated but makes more sense of the plot
date coordinates in=x,
xtick=data,
xticklabel style={rotate=90,anchor=near xticklabel},
x tick label as interval,
xticklabel=\tick -- \nexttick,
]
\addplot coordinates {
(2009-01-01, 050)
(2009-02-01, 100)
(2009-03-01, 100)
}
```



```
(2009-04-01, 100)
(2009-05-01, 040)
(2009-06-01, 020)
(2009-07-01, 000)
(2009-08-01, 035)
};
\end{axis}
\end{tikzpicture}
\end{document}
```

pgfplotstodo.tex:1529

Bug [open, Priority 5, Epic ‘]

xtick key still relies on PGF’s basic level foreach – and the numbers inside of it are not parsed as it seems.

pgfplotstodo.tex:1535

Bug [open, Priority 5, Epic ‘]

image externalization + \ref does not work out-of-the box. This affects the crossref pictures of pgfplots as well.

Idea: disable externalization for cross ref pictures!

pgfplotstodo.tex:1664

Bug [open, Priority 5, Epic ‘]

fillbetween + softclip: soft clip should return the input path if the input path is contained in the soft clip region

see http://tex.stackexchange.com/questions/195678/pgfplots-using-the-fillbetween-library/195697?noredirect=1#comment453086_195697

pgfplotstodo.tex:1717

Bug [open, Priority 5, Epic ‘]

extra ticks produce unwanted shifts of labels

I’m using pgfplots 1.10 and observe the following problem. The x label shifts down a bit if I introduce extra x ticks, even if their labels are empty. The following example produces the observed behavior:

```
\documentclass{standalone}
\usepackage{pgfplots}
\pgfplotsset{compat=newest}

\begin{document}

\begin{tikzpicture}
\begin{axis}[
width=4cm,
```

```

    xlabel=Test,
    axis x line=bottom,
    axis y line=left,
]
\addplot [black] {x^2};
\end{axis}
\end{tikzpicture}

\begin{tikzpicture}
\begin{axis}[
    width=4cm,
    xlabel=Test,
    axis x line=bottom,
    axis y line=left,
    extra x ticks={0},
    extra x tick labels={},
]
\addplot [black] {x^2};
\end{axis}
\end{tikzpicture}

\end{document}

```

It does not happen with the old, static, label placement (e. g. if I remove the `compat` setting). I was not able to test with 1.11, but there's nothing related mentioned in the release notes, if I did not overlook it. Any ideas what I'm missing or if it is a bug and how to work around it? I need two adjacent graphs in subfloats but only one of them has extra ticks, so the spacing should be equal to look reasonable. Adding an extra tick on the other plot helps, but the spacing looks better without, so that's not an option. And switching back to the old behavior means manually tweaking the distance, what makes no sense to me either.

pgfplotstodo.tex:1721

Bug [open, Priority 5, Epic “]

composed plot handlers (hist, boxplot, contour) need access to coordinate filters etc. during their first survey phase

pgfplotstodo.tex:1755

Bug [open, Priority 5, Epic “]

it seems as if the layer configuration does not really work:
`set layers={axis on top}` has a different effect than `axis on top`.

It seems as if I need `\pgfplotsgetlayerforstyle` somewhere when drawing the individual entities – setting `on layer` is not enough.

- pgfplotstodo.tex:1759 **Bug** [open, Priority 5, Epic ‘’]
scatter rgb is not documented
- pgfplotstodo.tex:1851 **Bug** [open, Priority 5, Epic ‘’]
REGRESSION: pgf image externalization is broken, see comments in
<https://sourceforge.net/p/pgf/bugs/229/>
- pgfplotstodo.tex:1908 **Bug** [open, Priority 5, Epic ‘’]
pgfplots fails to handle very small number ranges on logarithmic plots (i.e. if, say, xmin and xmax are very very close to each other).

see <http://www.mrunix.de/forums/showthread.php?76399-tikz-PGFplots-Fehler-dimension-too-large&p=358818#post358818>
- pgfplotstodo.tex:1914 **Bug** [open, Priority 5, Epic ‘’]
3d axes and y dir = reverse seems to corrupt the z ordering, see <http://texwelt.de/wissen/fragen/6131/pgfplots-3d-oberflachenproblem>
- pgfplotstodo.tex:1923 **Bug** [open, Priority 5, Epic ‘’]
ybar interval does not work well with nodes near coords

ybar interval has an artificial last coordinate. This will also receive nodes near coords.

See <http://tex.stackexchange.com/questions/181061/pgfplots-clipping-everything-outside-a-specific-area>
- pgfplotstodo.tex:1929 **Bug** [open, Priority 5, Epic ‘’]
ybar interval + nodes near coords: nodes are displaced.

The shift does not work here.
- pgfplotstodo.tex:1937 **Bug** [open, Priority 5, Epic ‘’]
Coordinate filtering + error bars do not work.

Expected behavior: error coordinates should be computed and coord filters should be applied to the result. Currently, filters are evaluated first and then error coordinates.

See <http://tex.stackexchange.com/questions/154084/how-to-scale-both-data-and-error-bars-in-pgfplots>

pgfplotstodo.tex:1943

Bug [open, Priority 5, Epic ‘’]

Old sampling no-go bug:

`\pgfplotsforeachgrouped \x in {0,1,...,5000}` is numerically instable (because I hesitated to do expensive float comparisons all the time...)

<http://tex.stackexchange.com/questions/183369/tikz-and-pgfplot-problem-with-plotting>

pgfplotstodo.tex:1948

Bug [open, Priority 5, Epic ‘’]

fillbetween / intersection lib bug: see minimal at

<http://tex.stackexchange.com/questions/180899/fillbetween-library-sometimes-works-and-sometimes-does-not-181224#181224>

pgfplotstodo.tex:1952

Bug [open, Priority 5, Epic ‘’]

`|\legendto name`— appears to be broken if the legend is empty (empty matrix?) TODO: verify that empty legends do not cause problems here!

pgfplotstodo.tex:1956

Bug [open, Priority 5, Epic ‘’]

`cube/size x` has no effect if used in a 2d axis

pgfplotstodo.tex:2089

Bug [open, Priority 5, Epic ‘’]

copy paste from the manual does not copy empty lines — which is quite bad for the 3d surface examples

This appears to be a known issue for pdf, with few available work-arounds. The listings package suffers from it as well (at least regarding trailing spaces/tabs); there are a couple of related questions at tex.stackexchange.com

A way might be to use `\usepackage{accsupp}` with something like

```
\documentclass{article}
```

```
\usepackage{accsupp}
```

```
\begin{document}
```

```
\long\def\XXX{A
```

```
^^J
```

```
^^J
```

```

B}
\BeginAccSupp[method=escape,ActualText=\XXX}
First line

second line
\EndAccSupp{}

\end{document}

```

Expected result: copy-pasting that segment should yield A (newline) B. But it does not work with newlines as it seems

One entry on tex.sx mentioned that Microsoft products can insert empty lines in copy-paste output (suggested solutions there was to generate such a pdf and include it as graphics unless I am mistaken)

I managed to get this up and running so far – but the result is unusable! both acrobat and xpdf get utterly confused unless one hits exactly on some invisible lines [\[see bugtracker/minimal_1.pdf\]](#)

```

\pdfcompresslevel=0
\documentclass{article}
\usepackage{pgfplots}
\usepackage{accsupp}
\pgfplotsset{compat=1.7}

\begin{document}

Test before

\begingroup
\catcode'\ =12\relax%
\catcode'\ ^M=13\relax%
\def^^M{^^J}%
\def\begin{\string\begin}%
\def\end{\string\end}%
\def\addplot{\string\addplot}%
\undef\copypastable%
\begin{tikzpicture}
  \begin{axis}
    \addplot3[surf] coordinates {
      (0,0,0) (1,0,0) (2,0,0) (3,0,0)

      (0,1,0) (1,1,0.6) (2,1,0.7) (3,1,0.5)

      (0,2,0) (1,2,0.7) (2,2,0.8) (3,2,0.5)
    };
  \end{axis}
\end{tikzpicture}%
}\endgroup

\BeginAccSupp{%
  method=escape,%
  ActualText={\copypastable}}
\begin{verbatim}
\begin{tikzpicture}
  \begin{axis}
    \addplot3[surf] coordinates {

```

```

(0,0,0) (1,0,0) (2,0,0) (3,0,0)

(0,1,0) (1,1,0.6) (2,1,0.7) (3,1,0.5)

(0,2,0) (1,2,0.7) (2,2,0.8) (3,2,0.5)
};
\end{axis}
\end{tikzpicture}
\end{verbatim}
\EndAccSupp{}%

Text middle

\begingroup
\catcode'\ =12\relax%
\catcode'\^^M=13\relax%
\def^^M{^^J}%
\def\begin{\string\begin}%
\def\end{\string\end}%
\def\addplot{\string\addplot}%
\xdef\copypastable{%
\begin{tikzpicture}
\begin{axis}[small,view={0}{90}]
\addplot3[surf,shader=interp,patch type=bilinear,
mesh/color input=explicit]
coordinates {
(0,0,0) [color=blue] (1,0,0) [color=green]

(0,1,0) [color=yellow] (1,1,1) [color=red]
};
\end{axis}
\end{tikzpicture}
}\endgroup

\BeginAccSupp{%
method=escape,%
ActualText={\copypastable}}
\begin{verbatim}
\begin{tikzpicture}
\begin{axis}[small,view={0}{90}]
\addplot3[surf,shader=interp,patch type=bilinear,
mesh/color input=explicit]
coordinates {
(0,0,0) [color=blue] (1,0,0) [color=green]

(0,1,0) [color=yellow] (1,1,1) [color=red]
};
\end{axis}
\end{tikzpicture}
\end{verbatim}
\EndAccSupp{}%

Text after
\end{document}

```

Problems here:

- one has to mark the right segments, and these can only be found by trial and error

- hitting the wrong one will copy nothing or only parts
- in the manual, I often had the wrong content in my clipboard (some older state of the clipboard, no idea where that came from)

pgfplotstodo.tex:2093

Bug [open, Priority 5, Epic ‘]

tikz intersections: the “store in macro” methods do not use global macros. Should they!?

pgfplotstodo.tex:2100

Bug [open, Priority 5, Epic ‘]

fill between:

```
addplot [draw=green!80,fill=green!20] fill between [of=lower and axis, soxft clip={(inters
```

produces no “unknown key soxft clip” error

pgfplotstodo.tex:2138

Bug [open, Priority 5, Epic ‘]

fill between / intersections lib bug: spurious intersections

<http://tex.stackexchange.com/questions/180127/stacking-plots-in-animation-using-fill-between-library-with-dynamic-calculation/180299#180299>

analysis in ~/tmp/bug_intersectionlibs.tex: problem seems to be the duplicate detection

problem: almost parallel lines:

problem: almost parallel lines:

```
\begin{tikzpicture}
\makeatletter
\def\A{%
  \pgfsyssoftpath@movetotoken{15.60165pt}{0.60783pt}%
\pgfsyssoftpath@linetotoken{0pt}{0pt}%
}%
\def\B{%
  \pgfsyssoftpath@movetotoken{15.60165pt}{0.81604pt}%
\pgfsyssoftpath@linetotoken{0.0pt}{0.33199pt}%
}%
\draw[blue] \pgfextra{\pgfsetpathandBB\A};
\draw[red] \pgfextra{\pgfsetpathandBB\B};
\pgfintersectionofpaths%
  {%
    \pgfsetpath\A
  }%
  {%
    \pgfsetpath\B
```

```

    }%

\pgfmathloop%
\ifnum\pgfmathcounter>\pgfintersectionsolutions\relax%
\else%
\draw[red] \pgfextra{\pgftransformshift{\pgfpointintersectionsolution{\pgfmathcounter}\mes
node[anchor=center] {\pgfmathcounter/\pgfintersectionsolutions};
\repeatpgfmathloop%

\end{tikzpicture}

```

pgfplotstodo.tex:2142

Bug [open, Priority 5, Epic ‘]

pgfplotstable appears to have problems with # in col names, compare
[http://tex.stackexchange.com/questions/175395/
how-can-csv-files-be-put-into-latex-without-having-to-adjust-much](http://tex.stackexchange.com/questions/175395/how-can-csv-files-be-put-into-latex-without-having-to-adjust-much)

pgfplotstodo.tex:2469

Bug [open, Priority 5, Epic ‘]

[http://tex.stackexchange.com/questions/104010/
why-does-loading-pgfplots-after-tikz-break-the-default-layers-in-a-tikzpicture](http://tex.stackexchange.com/questions/104010/why-does-loading-pgfplots-after-tikz-break-the-default-layers-in-a-tikzpicture)
is still active .

Solution: backgrounds lib must be loaded after pgfplots. Apparently, the
backwards layer stuff overwrites hooks of the backgrounds lib

pgfplotstodo.tex:2502

Bug [open, Priority 5, Epic ‘]

default tick labels are placed outside of displayed area if
unit vector `ratio*=1 1` is in effect

```

\documentclass{article}
\usepackage{pgfplots}
\usetikzlibrary{decorations.markings}
\pgfplotsset{compat=1.8}

\begin{document}

\begin{tikzpicture}
\begin{axis}[axis lines = middle,smooth,xlabel = $x$, ylabel = $y$, minor tick num =1, grid
\addplot[smooth, thick, -stealth,variable=\t, domain=0:2, ]
({t^2}, {t^4});

\addplot[thick, red,-stealth,samples=8,variable=\t, domain=0:2,quiver={
u=2*t, v=4*t^3, scale arrows=0.05,
}]
({t^2}, {t^4});

```



```

\end{axis}
\end{tikzpicture}

\end{document}

```

pgfplotstodo.tex:2515 **Bug** [open, Priority 5, Epic ‘] `|ytick=data|` does not work together with stacked plots because, by design, it merely considers coordinates of the *first* plot. That’s nonsense for stacked plots.

pgfplotstodo.tex:2539 **Bug** [open, Priority 5, Epic ‘] Tick labels suffer from inexact arithmetics in Tikz foreach:

KAPUTT:

```
\foreach \x in {1,1.1,...,2} {\x\par}
```

OK:

```
\foreach \x in {1,1.1,...,2.001} {\x\par}
```

pgfplotstodo.tex:2543 **Bug** [open, Priority 5, Epic ‘] `ytick=data` combined with minor y tick num does not work as expected: minor tick lines will be skipped below the lowest limit.

pgfplotstodo.tex:2549 **Bug** [open, Priority 5, Epic ‘] `pgfplotstable` does not apply `postproc cell content in every row` styles
see <http://tex.stackexchange.com/questions/111492/postprocess-row-with-pgfplotstable>

pgfplotstodo.tex:2555 **Bug** [open, Priority 5, Epic ‘] no markers: it appears to be impossible to switch off markers, only for scatter plots.
See <http://tex.stackexchange.com/questions/105850/pgfplots-points-with-no-marks-but-errorbars>

pgfplotstodo.tex:2597

Bug [open, Priority 5, Epic ‘’]

|...|and rounding:

Generell erscheint mir die ...-Syntax nicht robust. Bei kleinen, durchaus nicht ungewöhnlichen, Intervallen kommt es zu Rundungsfehlern:

Hauptgitter:

```
ytick={0.99,1.00,1.01,1.02,1.03,1.04,1.05,1.06,1.07,1.08}
```

Hilfsgitter:

```
minor ytick={0.99,0.991,...,1.08}
```

Frht dazu, dass die Hilfslinien mit zunehmender Gre immer weiter von den Hauptgitterlinien verschoben sind, obwohl diese aufeinanderliegen sollten. Mit Hilfsgitter komplett ausgeschrieben:

```
minor ytick={0.99,0.991,0.992,0.993,.....,1.08}
```

passt es. Die ...-Syntax ist daher absolut mit Vorsicht zu genieen.

pgfplotstodo.tex:2601

Bug [open, Priority 5, Epic ‘’]

box plots with draw direction=y and xtick=data fail to provide the correct xtick locations

pgfplotstodo.tex:2626

Bug [open, Priority 5, Epic ‘’]

presets for mark size and tiny / footnotesize are wrong

pgfplotstodo.tex:2644

Bug [open, Priority 5, Epic ‘’]

clipping of tick lines does not respect the line width of the axis lines.

<http://tex.stackexchange.com/questions/91517/how-to-make-the-tick-thickness-as-the-axis-line/91645#91645>

pgfplotstodo.tex:2668

Bug [open, Priority 5, Epic ‘’]

Inf geht nicht im math parser:

```
\documentclass[a4paper]{article}
```

```
\usepackage{pgfplots}
```

```

\begin{document}

\pgfmathfloatparsenumber{Inf}
\pgfmathresult

{
\pgfkeys{/pgf/fpu}
\pgfmathparse{Inf}
\pgfmathresult
}

\end{document}

```

pgfplotstodo.tex:2687 **Bug** [open, Priority 5, Epic ‘’]
`\disablelogfilter,ymax=1e-6, ymode=log—` fails. Apparently, the coordinate is not parsed at all.

pgfplotstodo.tex:2699 **Bug** [open, Priority 5, Epic ‘’]
`\closedcycle` does not work together with jumps / interrupted plots

pgfplotstodo.tex:2723 **Bug** [open, Priority 5, Epic ‘’]
auto tick label assignment can sometimes produce strange results:

[see [bugtracker/minimal_2.pdf](#)]

```

\documentclass{article}
\usepackage{pgfplots}
\pgfplotsset{compat=1.6.1}

\begin{document}

\begin{tikzpicture}
\begin{axis}[%
scale only axis,
xmin=0, xmax=0.02,
ymin=-1, ymax=1]
\end{axis}
\end{tikzpicture}%
\end{document}

```

See also the examples for boxplots in the manual

pgfplotstodo.tex:2765 **Bug** [open, Priority 5, Epic ‘’]
`the3d clip path` is sometimes bad: perhaps it should be the bounding box instead!?




Figure 44: Mesh plot. `meshPlot`

`pgfplots.stodo.tex:2797`

Bug [open, Priority 5, Epic ‘’]

One cannot manually load a table inside of a `pgfplots` axis if it contains empty lines: the scanline callback is active

`pgfplots.stodo.tex:2801`

Bug [open, Priority 5, Epic ‘’]

`|ybarlegend|`— does not contain `ybar` (sourceforge 3482770)

`pgfplots.stodo.tex:2805`

Bug [open, Priority 5, Epic ‘’]

`|refstyle|` does only include partial information of the reference style. (sourceforge 3482770)

`pgfplots.stodo.tex:2811`

Bug [open, Priority 5, Epic ‘’]

Using square brackets as first char inside of `\legend` leads to a failure: `\legend{[\ion{Ne}{2}],...}`.

Cause: the `\legend` command does not properly insert `[]` in front of every entry (as it ought to).

`pgfplots.stodo.tex:2817`

Bug [open, Priority 5, Epic ‘’]

Adding `error bars/.cd` to `\addplot` options causes the `\ref` image to fail.

The problem is the key filtering apparently: it discards the `/pgfplots/.cd` but leaves the `error bars/.cd`.

pgfplotstodo.tex:2821

Bug [open, Priority 5, Epic ‘’]
quiver plots: the clip path does not respect arrow paths

pgfplotstodo.tex:2878

Bug [open, Priority 5, Epic ‘’]
Alignment bug: axis x line=middle combined with a yshift shifts the xlabel incorrectly: [see [bugtracker/minimal_3.pdf](#)]

```
\documentclass{report}
\usepackage{pgfplots}
\pgfplotsset{compat=1.3}

\begin{document}
\begin{tikzpicture}
\draw (0,0) circle (5pt);
\begin{scope}[yshift=-3cm]
\begin{axis}[width=10cm,height=3cm,xlabel={x},
axis x line = middle]
\addplot coordinates {
(0,1) (1,-1) (2,1)
};
\end{axis}
\end{scope}
\end{tikzpicture}
\end{document}
```

Using `xlabel style = {yshift=3cm}` in the plot will correctly position the x label (to its default position).

pgfplotstodo.tex:2955

Bug [open, Priority 5, Epic ‘’]
cannot provide clip path usage in pgfplots commands because of the nested scopes.

to reproduce, try to give `\addplot+[/tikz/clip]` to some plot.

pgfplotstodo.tex:2963

Bug [open, Priority 5, Epic ‘’]
`|\pgfplotsforeachungrouped|` cannot be combined with three or more arguments like `\foreach`

pgfplotstodo.tex:3062

Bug [open, Priority 5, Epic ‘’]
the below example of a latex file gives the following error upon the 2nd run of latex. The first run works fine. This happens both when running `dvilualatex` and just `latex`, both from `TeXLive 2011`.

The error:

...

```

(/usr/local/texlive/2011/texmf-dist/tex/generic/tex4ht/color.4ht)
(/usr/local/texlive/2011/texmf-dist/tex/generic/tex4ht/html4.4ht)
(/usr/local/texlive/2011/texmf-dist/tex/generic/tex4ht/html4-math.4ht))
(./epub.aux)
! Missing \endcsname inserted.
<to be read again>
\protect
1.30 \ref{govconsumptionlegend}

?

\makeatletter

\def\HCode{\futurelet\HCode\HChar}\def\HChar{\ifx"\HCode\def\HCode"##1"{\Link##1}\expandafter

\makeatother

\HCode "xhtml,png,charset=utf-8".a.b.c.

\documentclass[11pt,a4paper]{book}

\def\pgfsysdriver{pgfsys-tex4ht.def}
\usepackage{pgfplots}

\pgfplotsset{width=\textwidth,compat=1.3,every axis/.append style={font=\footnotesize},cyc

\begin{document}
\begin{tikzpicture}

\begin{axis}[ylabel=\%,x tick label style={/pgf/number format/1000 sep=},ymin=0,xmin=1950
\addplot[smooth,solid] coordinates {
(1950,12.98732304) (1951,11.18937899) (1952,10.63447043) (1953,11.25741618) (1954,11.35201
};
\addlegendentry{Country 1}
\addplot[smooth,dotted] coordinates {
(1950,8.90574995) (1951,9.181850378) (1952,9.4040808) (1953,9.790597533) (1954,9.766571438
};
\addlegendentry{Country 2}
\end{axis}\end{tikzpicture}

\ref{govconsumptionlegend}

\end{document}

```

pgfplotstodo.tex:3311

Bug [open, Priority 5, Epic “]

<http://groups.google.at/group/comp.text.tex/msg/adcb1d071c2cba40>

If I use a `yshift` in a scope to draw two graphs superimposed, the x label in the second plot (the one in the `yshift` scope) is not positioned correctly. I need to manually add another `yshift`, with the same value in the opposite direction, to get the label at the correct place. This happens if the `axis x line = middle` option is used. Without that option, the x label is positioned correctly. Example follows: [\[see bugtracker/minimal_4.pdf\]](#)

```

\documentclass{article}

\usepackage{pgfplots}

\pgfplotsset{compat=1.3}

\begin{document}

  \begin{tikzpicture}
    \begin{axis}[width=10cm,height=3cm,xlabel={\$x\$}]
      \addplot coordinates {
        (0,1) (1,-1) (2,1)
      };
    \end{axis}
    \begin{scope}[yshift=-3cm]
      \begin{axis}[width=10cm,height=3cm,xlabel={\$x\$},
        axis x line = middle]
        \addplot coordinates {
          (0,1) (1,-1) (2,1)
        };
      \end{axis}
    \end{scope}
  \end{tikzpicture}
\end{document}

```

Using `xlabel style = {yshift=3cm}` in the second plot will correctly position the x label (to its default position).

Gab

pgfplotstodo.tex:3487

Bug [open, Priority 5, Epic ‘’]

after using a preset key (`milli`) with x SI prefix, Next, I want to switch to the normal mode, so I write simply: `x SI prefix=none`, unfortunately the ‘none’ value is undefined and the compilation can not proceed

pgfplotstodo.tex:3553

Bug [open, Priority 5, Epic ‘’]

check y tick scale label for 2nd y axis

pgfplotstodo.tex:3570

Bug [open, Priority 5, Epic ‘’]

groupplots + extra braces or foreach are incompatible.

- pgfplotstodo.tex:3574 **Bug** [open, Priority 5, Epic ‘’]
numplotspertype and forget plot and ybar interval yields errors.
- pgfplotstodo.tex:3580 **Bug** [open, Priority 5, Epic ‘’]
expression plotting and empty ‘y’ results in errors. Perhaps it would be better to handle that explicitly somehow? (occurs for hist when one input line is empty)
- pgfplotstodo.tex:3600 **Bug** [open, Priority 5, Epic ‘’]
/pgfplots/samples at and /tikz/samples at work on the same axe. Tantau says that this key support foreach statement and thus the dots notation. However, when I want to use two or more different dots notation within pgfplots, latex crashes ! Here is an example which clarify this issue :
`\addplot+[mark=none,variable={\t}, samples at = {\foreach \x in {0,10,...,180,200,...340}`
- pgfplotstodo.tex:3610 **Bug** [open, Priority 5, Epic ‘’]
groupplots: mixing 2d/3d in one groupplot doesn’t reset ‘zmin,zmax’ ?
- pgfplotstodo.tex:3631 **Bug** [open, Priority 5, Epic ‘’]
3D axes: it is difficult to get an 1:1 correspondence to tikz.
- pgfplotstodo.tex:3647 **Bug** [open, Priority 5, Epic ‘’]
3D axis: provide support for manual axis configuration, - depth (n vector), - foreground/background, - tick label axes, - ...
- pgfplotstodo.tex:3676 **Bug** [open, Priority 5, Epic ‘’]
plot graphics: `\ref` legend doesn’t work properly
- pgfplotstodo.tex:3697 **Bug** [open, Priority 5, Epic ‘’]
ternary axes: the ‘marker clipping’ doesn’t work (naturally)
- pgfplotstodo.tex:3707 **Bug** [open, Priority 5, Epic ‘’]
polar axes:
- ✓ is wrong since ‘near ticklabel’ anchor uses pointunitx which is not correctly initialised for polar axes.

- axis equal
- ✓ data scaling needs to be disabled for X axis.
- ✓ auto tick labels work only for the case of disabled data scaling

pgfplotstodo.tex:3712 **Bug** [open, Priority 5, Epic ‘’]
contour: the table/meta=2 default is wrong.

pgfplotstodo.tex:3725 **Bug** [open, Priority 5, Epic ‘’]
dimension too large sanity checking: TeX uses the maximum value instead.
Perhaps that can be checked?

pgfplotstodo.tex:3761 **Bug** [open, Priority 5, Epic ‘’]
the quiver/scale arrows thing might need an ”auto” option. If I don’t add it
now, it’ll probably never work in the future.

pgfplotstodo.tex:3766 **Bug** [open, Priority 5, Epic ‘’]
‘1.23456e4;’ in a log plot resulted in hard-to-read error messages. Improve
sanity checking here.

pgfplotstodo.tex:3785 **Bug** [open, Priority 5, Epic ‘Usability’]
avoid dimension too large errors which occur due to a data range restrictions.
Example: data range = 0:6000 view range = 0:1 \rightsquigarrow results in error. But that’s
easy to detect! Just compute the point coordinate in float (after the scaling is
complete). Then, install a filter somewhere. perhaps an ”a posteriori” filter in
the pointxyz command?

DUPLICATE: the nasty dimension-to-large message could probably be
avoided if pgfplots would simply clip the results to TeX’s range

pgfplotstodo.tex:3799 **Bug** [open, Priority 5, Epic ‘’]
|yticklabels={<list>}, extra y ticks=...— is incompatible since the extra
ticks share the same tick typesetting routine (which, in turn, queries the |list_i).

pgfplotstodo.tex:3813 **Bug** [open, Priority 5, Epic ‘’]
The ’text depth’ in legend entries is incompatible with ’text width’. The
problem: text width is implemented using `\begin{minipage}[t]` so its
contents is all in the depth. Setting text depths overrides the height!

- pgfplotstodo.tex:3823 **Bug** [open, Priority 5, Epic ‘’]
one can't provide 'disable log filter' to addplot (but it might be interesting)
- pgfplotstodo.tex:3827 **Bug** [open, Priority 5, Epic ‘’]
FPU: atan doesn't check for unbounded inputs.
- pgfplotstodo.tex:3832 **Bug** [open, Priority 5, Epic ‘’]
unbounded inputs: improve warning messages: they should not contain low level FPU args.
- pgfplotstodo.tex:3838 **Bug** [open, Priority 5, Epic ‘’]
the user interface to set 'tickwidth=0' for a SINGLE axis is not very good: it seems one needs 'xtick style=/pgfplots/tickwidth=0' to do so... ↪ can be solved if tickwidth has a family, I guess. Something like 'draw' which will not be pulled by pgfplots. But then remains a problem of key paths.
- pgfplotstodo.tex:3846 **Bug** [open, Priority 5, Epic ‘’]
I have seen that 'plot table' with very large files can produce pool size problems – even if the coordinates are all filtered away. In other words: the code can't simply read a file and throw its contents away. The problem appears to be some math parsing using the table/x expr and friends. 'pool size = names of control sequences and file name' ↪ the math parser could be improved with ifcurname
- pgfplotstodo.tex:3861 **Bug** [open, Priority 5, Epic ‘’]
providing zmin/xmax to an axis activates 3D mode, ok – but lower dimensional input routines appear to fail.
- pgfplotstodo.tex:3865 **Bug** [open, Priority 5, Epic ‘’]
one can't provide 'scale' as argument to a (3d) axis
- pgfplotstodo.tex:3874 **Bug** [open, Priority 5, Epic ‘’]
it may still happen that log-axes get only *one* tick label (in my case $10^{-0.2}$). That should never happen. The range is about $y_{\min}=4.7e-1$, $y_{\max}=9.5e-1$

- `pgfplotstodo.tex:3878` **Bug** [open, Priority 5, Epic ‘']
log samples in plot expression for 3D plots
- `pgfplotstodo.tex:3882` **Bug** [open, Priority 5, Epic ‘']
different log bases and gnuplot
- `pgfplotstodo.tex:3896` **Bug** [open, Priority 5, Epic ‘']
I tried placing a named coordinate inside one axis and using it in another. It failed.

CF: The axis is drawn inside of its own picture which will only be shifted if everything has been drawn. That will be the origin of this problem I guess

Miraculously I can use the coordinate outside axis env. So I have reached the following solution:
- `pgfplotstodo.tex:3902` **Bug** [open, Priority 5, Epic ‘']
plot coordinates doesn't check too well if 1. `addplot3` is used but only two coords are given 2. `addplot` is given but three coordinates are provided (also for plot expression)
- `pgfplotstodo.tex:3915` **Bug** [open, Priority 5, Epic ‘']
the compat things are not yet complete: I wanted to check when it is really necessary (for example if 'x dir' is used)
- `pgfplotstodo.tex:3920` **Bug** [open, Priority 5, Epic ‘']
the nodes near coords feature produces unexpected results when used together with markers \rightsquigarrow this is due to the default configuration of scatter plots.
- `pgfplotstodo.tex:3931` **Bug** [open, Priority 5, Epic ‘']
the ybar style won't be set inside of `\label{}`
- `pgfplotstodo.tex:3936` **Bug** [open, Priority 5, Epic ‘']
axis equal for semilog plots is not correct (?)

pgfplotstodo.tex:3944 **Bug** [open, Priority 5, Epic ‘] backwards compatibility problem: axis descriptions can’t contain /pgfplots/ styles any longer! This is a key path issue :-)

pgfplotstodo.tex:3949 **Bug** [open, Priority 5, Epic ‘] BUG: in empty axes, ‘xtick=\empty’ is ignored.

pgfplotstodo.tex:3966 **Bug** [open, Priority 5, Epic ‘] The automatic tick labeling sometimes produces inconsistent or confusing labels: 1. engineering and fixed number style are mixed up. 2. If range of an axis is so small that the labels differ only on the third decimal, still only two decimals are used.

pgfplotstodo.tex:3981 **Bug** [open, Priority 5, Epic ‘] 3D: error bars and stacked plots need to be updated.

Is this still current? There has been a major revision some time ago...

pgfplotstodo.tex:4019 **Bug** [open, Priority 5, Epic ‘] addplot3 vs addplot:

3D: the use of `\addplot3` and `\addplot` is not sanitized properly

Possibilities:

- used `\addplot` when `\addplot3` should have been used
- used `\addplot3` where `\addplot` should have been used.

What can happen here!? Shouldn’t this work in every case?

- The "xtick" value is not applied unless there is a coordinate in the x range: $\$ \leadsto \$$ that’s the handling of empty figures...

not working:

```
\begin{axis}[xtick=0]
\end{axis}
```

not working:

```
\begin{axis}[xmin=-5,xmax=5,xtick=0]
\end{axis}
```

not working:

```
\begin{axis}[xmin=-5,xmax=5,xtick=0]
\addplot coordinates { (-10, 0) };
\end{axis}
```

working:

```
\begin{axis}[xmin=-5,xmax=5,xtick=0]
\addplot coordinates { (0, 0) };
\end{axis}
```

- pgfplotstodo.tex:2352 **Bug** [open, Priority 4, Epic ‘’]
 adding a post action with decoration to a pgfplots style results in an error if markers are active
- pgfplotstodo.tex:1539 **Bug** [open, Priority 3, Epic ‘’]
 TikZ wastes time during its point evaluations (i.e. expressions of sorts (1,2)): it calls `tikz@checkunit` in order to check for units and throws the math result away (and computes it again afterwards).
- pgfplotstodo.tex:1843 **Bug** [open, Priority 3, Epic ‘’]
 contour plot handler does not allow ‘name path’.
- pgfplotstodo.tex:2304 **Bug** [open, Priority 3, Epic ‘’]
 fill between: `soft clip={domain=1:2}` might fail if the function in question touches the y boundary within the domain. In this case, the soft clip path produces unwanted side-effects.

 Cure: enlarge the soft clip path generated by `domain`. It should be bigger than the function in question (with respect to y)

 (I have a not-quite-minimal example in my tmp folder)
- pgfplotstodo.tex:2413 **Bug** [open, Priority 3, Epic ‘’]
 Usability issues around histograms: <http://tex.stackexchange.com/questions/151411/histogram-frequeintion-polygon/151551#151551>

[\[see bugtracker/minimal_5.pdf\]](#)


```

\documentclass{standalone}
\usepackage{tikz}
\usetikzlibrary{calc,intersections,through,backgrounds,snakes}
\usepackage{pgfplots}
\pgfplotsset{compat=1.8}
\usepgfplotslibrary{statistics}
\begin{document}
\begin{tikzpicture}
\begin{axis}[
width=1*\textwidth,
height=8cm,
ymin=0,
ymax=7,
title=Histogram lichaamslengte,
ybar interval,
xticklabel={[\pgfmathprintnumber\tick--\pgfmathprintnumber\nexttick []],
\addplot+[hist={bins=4, data max=12,data min=0}]
table[row sep=\\,y index=0] {
data\\
1\\ 2\\ 1\\ 5\\ 4\\ 10\\ 4\\ 5\\ 7\\ 10\\ 9\\ 8\\ 9\\ 9\\ 11\\

```

```

};

\addplot[
  %
  % there seems to be a bug in pgfplots which would shift the two
  % 'hist' plots as if both were bar plots.
  % This is one possible work-around:
  forget plot,
  %
  mark=*,
  hist={bins=4, data max=12,data min=0,
    % this here should *not* become an ybar interval:
    handler/.style={sharp plot},intervals=false,
  },
  %
  % .. but since the other plot is shown with intervals, we should
  % shift this here accordingly:
  shift={(axis direction cs:1.5,0)},
]
table[row sep=\\,y index=0] {
data\\
1\\ 2\\ 1\\ 5\\ 4\\ 10\\ 4\\ 5\\ 7\\ 10\\ 9\\ 8\\ 9\\ 9\\ 11\\
};
\end{axis}
\end{tikzpicture}
\end{document}

```

Problems:

- point meta uses the wrong values (try out nodes near coords)
- ybar interval is active for the second plot
- interval=false should be deduced automatically

pgfplotstodo.tex:2575

Bug [open, Priority 3, Epic ‘] units and square brackets

Dann habe ich noch eine Anmerkung bzgl. der Verwendung von Einheiten in Achsbeschriftungen

----- Zitat

ANMERKUNG;

Die eckigen Klammern drfen nicht um Einheitenzeichen gesetzt werden. Angaben wie [kg] sind

----- Ende Zitat

’DIN 461: Graphische Darstellung in Koordinatensystemen’ gibt Beispiele, wie es gemacht we

Hintergrund: formaler Zusammenhang ist $X=\{X\}[X]$. Das heit: $X=5N \rightarrow \{X\}=5$ und $[X]=N$. Unsinn

Wie gesagt: leider eine sehr schlechte Angewohnheit und den meisten unbekannt oder schlich

While I understand the problem, I am inclined to keep it as-is... I cannot break backwards compatibility now, and I hear few complaints. I suppose the units stuff could be reviewed at some time

pgfplotstodo.tex:2691 **Bug** [open, Priority 3, Epic ‘’]
gnuplot interface: unbounded coords are not recognized as such (type=u).

pgfplotstodo.tex:2759 **Bug** [open, Priority 3, Epic ‘’]
x tick scale label for style `tiny` has an unsuitable shift

pgfplotstodo.tex:3350 **Bug** [open, Priority 3, Epic ‘’]
`\addplottable[blue]`— ignores the color options!

pgfplotstodo.tex:4069 **Bug** [open, Priority 3, Epic ‘’]
3D case : tick/grid lines are on top of the axis lines. This leads to poor quality.

... but nobody has ever complaint so far

pgfplotstodo.tex:1048 **Bug** [open, Priority 2, Epic ‘’]
The following fails to compile with `lualatex` (due to the double quotes apparently). It works in `pdflatex`

Low prio because the point meta is not actually used – and if it is used correctly, it works in both `lualatex` and `pdflatex`

```
\documentclass{standalone}
\usepackage{pgfplots}
\pgfplotsset{%
  compat=newest,
}
\begin{document}
\begin{tikzpicture}
\begin{axis}[
  %point meta=explicit symbolic,
  %nodes near coords=\pgfplotspointmeta,
]
\addplot table[x index={1}, y expr=\coordindex, header=false, meta index={0}] {
"i" 62.099
"i" 62.046
"i" 56.304
"i" -44.258
"2" -28.826
```

```

"i" 18.740
"i" -14.653
"i" 14.402
"i" -12.907
"i" 12.295
};
\end{axis}
\end{tikzpicture}
\end{document}

```

pgfplotstodo.tex:1300

Bug [open, Priority 2, Epic ‘’]

It seems that quiver combined with `every arrow` and `--{Latex[width=2pt]}` produces some unwanted side effect:

it produces entirely different output than without the `arrow spec`

```

\documentclass{standalone}
\usepackage{pgfplots}
\pgfplotsset{compat=1.11}
\usetikzlibrary{arrows.meta}
\begin{document}
\begin{tikzpicture}
\begin{axis}[domain=-3:3, view={0}{90}]
\addplot3[blue,
point meta=x,
quiver={
u=-x,
v=-y,
scale arrows=0.085,
every arrow/.append style={%
--{Latex[width=2pt]}},
%arrows={--{Latex[width=2pt,length=3pt]}},
},
},
samples=21,
]
{0};
\end{axis}
\end{tikzpicture}

```

```

\end{document}

```

pgfplotstodo.tex:2235

Bug [open, Priority 2, Epic ‘’]

context + color mix produces spurious shifts

I'm using pgfplots to create some bar charts with error bars in ConTeXt, and I want to use custom colours for them. This works, but if I mix a custom colour with another colour, it results in a gap between the error bar line and the error bar mark. If two custom colours are mixed, the gap seems to be doubled. Mixing with predefined colours works normally. MWE:

```
\usemodule[tikz]
\usemodule[pgfplots]

\definecolor [Blue] [h=3465a4]
\definecolor [White] [h=ffffff]

\pgfplotsset{compat=newest}

\starttext
\starttikzpicture
\startaxis[ybar, error bars/y dir=both, error bars/y explicit]
\addplot+[blue!50!white] coordinates {(1,5) +- (0,3)};
\addplot+[Blue] coordinates {(1,5) +- (0,3)};
\addplot+[Blue!50!white] coordinates {(1,5) +- (0,3)};
\addplot+[Blue!50!White] coordinates {(1,5) +- (0,3)};
\stopaxis
\stoptikzpicture
\stoptext
```

Here you can see the result:
<http://666kb.com/i/c186t0mfpin35tth7.png>

pgfplotstodo.tex:2348

Bug [open, Priority 2, Epic ‘]

Adding user decorations to axis lines might interfere with the discontinuities which are also decorations, compare

http://tex.stackexchange.com/questions/160936/random-decoration-of-plot-axis-messes-up-direction-of-axis-arrow/161025#comment368659_161025

I already added Jake's workaround to the code, but might still need more cleanup (and for non-centered axis lines as well)

pgfplotstodo.tex:2417

Bug [open, Priority 2, Epic ‘]

Loading a pgfplots library via `\usetikzlibrary{pgfplots...}` fails unless pgfplots is loaded. This should be reported properly (or perhaps load pgfplots implicitly?)

- pgfplotstodo.tex:2461 **Bug** [open, Priority 2, Epic ‘’]
 some issue regarding extra ticks in log axes has been reported in <http://tex.stackexchange.com/questions/148703/bug-pgfplots-extra-ticks>
- pgfplotstodo.tex:2526 **Bug** [open, Priority 2, Epic ‘’]
 The combination of 3d unit vectors and `scale mode=stretch to fill` is useful, but unsupported.
- I made a brief experiment to verify that it does something useful if
- the data scaling is disabled in `setunitvector`
 - the first if branch of `...@prepare@plotbox@limits` is activated.
- References: <http://tex.stackexchange.com/questions/139686/controlling-orientation-in-3d-pgf-plots>
- pgfplotstodo.tex:2606 **Bug** [open, Priority 2, Epic ‘’]
 boxplots: predefined legend entries need to be improved
- pgfplotstodo.tex:2695 **Bug** [open, Priority 2, Epic ‘’]
 gnuplot interface + raw gnuplot does not handle log scale properly (?)
- pgfplotstodo.tex:2735 **Bug** [open, Priority 2, Epic ‘’]
 new layered graphics stuff: the style changes of the layer config are read too late; it is impossible to overwrite them within the same axis (for example using `set layers,tick style={on layer=...}`)
- pgfplotstodo.tex:3074 **Bug** [open, Priority 2, Epic ‘’]
 #3213889 hyperref boxes are in wrong position for vertical labels
- see <http://tex.stackexchange.com/questions/13364/how-to-make-pgfplots-vertical-labels-have-proper-hyperref-erence-box> for problem description and potential fixes
- pgfplotstodo.tex:3169 **Bug** [open, Priority 2, Epic ‘’]
 The clipping of tick lines uses the middle of axis lines; it does not incorporate the line width of the axis lines. [see [bugtracker/minimal_6.pdf](#)]

```

\documentclass{article}
\usepackage{pgfplots}
\pgfplotsset{compat=1.3,
  every axis/.append style={semithick},
  every tick/.append style={semithick,color=black},
  tick align=outside
}
\begin{document}
  \thispagestyle{empty}
  \begin{figure}[p]
    \centering
    \begin{tikzpicture}
      \begin{axis}[xmin=0,
        xmax=30,
        ymin=0,
        ymax=1.2
      ]
        \end{axis}
      \end{tikzpicture}
    \end{figure}
  \end{document}

```

pgfplotstodo.tex:3196

Bug [open, Priority 2, Epic “]

can someone confirm the following behavior. The y label of a plot gets truncated in some circumstances if the external library is used. This happens for me if no title is specified for a plot. Consider the following example:

[see [bugtracker/minimal_7.pdf](#)]

```

\documentclass[11pt,a4paper]{article}

\usepackage{tikz}
\usepackage{pgfplots}

\pgfplotsset{compat=1.3}
\usepgfplotslibrary{external}
\tikzexternalize[force remake]

\begin{document}
\begin{tikzpicture}
\begin{axis}[y tick scale label style={inner sep=1pt}]
\addplot {x * 10^8};
\end{axis}
\end{tikzpicture}
\end{document}

```

pgfplotstodo.tex:3605

Bug [open, Priority 2, Epic “]

potential incompatibility: clickable and external. The clickable lib writes into pgfplots.djs which might cause multithreaded problems.

pgfplotstodo.tex:3718

Bug [open, Priority 2, Epic “]

OK : 'every node near coord/.append style=scale=0.7' NOT OK: 'every node near coord/.append style=scale=0.7,ybar' -> sequence of shift and scale matters ...

- pgfplotstodo.tex:3731 **Bug** [open, Priority 2, Epic ‘']
view=090 and enlargelimits=auto is not always satisfactory: it disables enlarged limits, but for contours, I'd like to have it. What is to do?
- pgfplotstodo.tex:3752 **Bug** [open, Priority 2, Epic ‘']
contour external doesn't handle explicitly provided matrix data (mesh/rows and mesh/cols) yet.
- pgfplotstodo.tex:3756 **Bug** [open, Priority 2, Epic ‘']
contour external doesn't handle the ordering flag correctly.
- pgfplotstodo.tex:3771 **Bug** [open, Priority 2, Epic ‘']
the title style for 'footnotesize' is not as I want it to: it doesn't respect the depth below the baseline. Or does it need a `\strut`?
- pgfplotstodo.tex:3991 **Bug** [open, Priority 2, Epic ‘']
interp shader is displayed transparently in evince

Bug in evince (for sure). What is to be done?
- pgfplotstodo.tex:1847 **Bug** [open, Priority 1, Epic ‘']
contour plot handler does not allow to specify draw and fill – which might be useful if just one contour is drawn/filled
- pgfplotstodo.tex:2427 **Bug** [open, Priority 1, Epic ‘']
The special feature
`patch,patch type=quadratic spline, point meta=none` which produces global paths appears to duplicate the low level path. I suppose this can only be seen in the resulting pdf file or in a debugger, but it makes a big difference when used together with decorations or fill between.

This feature should be documented in more places as well.

FOUND IT: the problem is stated incorrectly: the path is generated once (and only once). BUT: `\tikz@mode` is invoked twice, once by the mesh plot handler

and once by tikz. This is idempotent, in general – but not if we have name `path=A` in place! In this case, the softpath will be *appended* every time `\tikz@mode` is being executed.

INACTIVE: at the time of this writing, the offending “append” feature of name `path` is inactive; this bug does not happen anymore

pgfplotstodo.tex:2452

Bug [open, Priority 1, Epic “]]

`\usepackage[gray]{xcolor}` does not seem to work as good as for `cmlyk...` in particular, the default color map is not being converted correctly!? Probably because `xcolor` does not convert the colors if they are RGB

This appears to be irrelevant because RGB gray colors can be translated losslessly to scalar gray values!?

pgfplotstodo.tex:2769

Bug [open, Priority 1, Epic “]]

Internal `coordmath` framework: it is not used everywhere

pgfplotstodo.tex:2793

Bug [open, Priority 1, Epic “]]

`\lognumber` format code— is a global variable and cannot be set for individual axes.

This applies to `log ticks` with `fixed point` as well.

pgfplotstodo.tex:3095

Bug [open, Priority 1, Epic “]]

CRASH: [see [bugtracker/minimal_8.pdf](#)]

```
\begin{tikzpicture}
  \begin{axis}[
    scale mode=scale uniformly,
    x={(1pt,0pt)},
    y={(-0.5pt,0.5pt)},
    z={(0pt,1pt)},
  ]
  % addplot3 works (with 3d coords):
  \addplot coordinates {
    (0,0) (1,0) (0,1)
  };
\end{axis}
\end{tikzpicture}
```

pgfplotstodo.tex:3140

Bug [open, Priority 1, Epic ‘’]

Using 0 in pgfplots coordinate systems does not necessarily mean “no offset”.

This is misleading. Bug sourceforge #3168030: [see [bugtracker/minimal_9.pdf](#)]

```

\documentclass[a4paper]{article}
\usepackage{german}
\usepackage[utf8]{inputenc}

\usepackage{pgfplots}

\usepackage{pgfplotstable}
\usepackage{booktabs}
\usepackage{array}
\usepackage{colortbl}

\begin{document}

\begin{tikzpicture}
  \begin{axis}[enlarge x limits=false, extra description/.code={\draw[very thick] (axis cs:2.5,0) -- ++(rel
    \addplot coordinates{
                                (0,1)
                                (1,2)
                                (2,3)
                                (3,4)
                                (4,5)};

  \end{axis}
\end{tikzpicture}

\begin{tikzpicture}
  \begin{axis}[enlarge x limits=true, extra description/.code={\draw[very thick] (axis cs:2.5,0) -- ++(rel
    \addplot coordinates{
                                (0,1)
                                (1,2)
                                (2,3)
                                (3,4)
                                (4,5)};

  \end{axis}
\end{tikzpicture}
\end{document}

\end{document}

```

pgfplotstodo.tex:3268

Bug [open, Priority 1, Epic ‘’]

The legend has the `text depth=0.15em` initial configuration, which is extremely bad for legend entries with huge depth (large fractionals or formulas?)

pgfplotstodo.tex:3388

Bug [open, Priority 1, Epic ‘’]

The mark `list` produces a lot of

```

\XC@edef #1#2->\begingroup \ifnum \catcode ‘\!=13 \edef !{\string !}\fi \ifnum \catcode ‘\
[.....]

```

```

{\if}

\@@tmp ->.!80!black
{true}
{the character !}
Missing character: There is no ! in font nullfont!
{the character 8}
Missing character: There is no 8 in font nullfont!
{the character 0}
Missing character: There is no 0 in font nullfont!
{the character !}
Missing character: There is no ! in font nullfont!
{the character b}
Missing character: There is no b in font nullfont!
{the character l}
Missing character: There is no l in font nullfont!
{the character a}
Missing character: There is no a in font nullfont!
{the character c}
Missing character: There is no c in font nullfont!
{the character k}
Missing character: There is no k in font nullfont!
{\def}
{\else}

```

bugs. Probably fixed with more recent version of xcolor?

pgfplotstodo.tex:3455

Bug [open, Priority 1, Epic “] providing `\legend{}` without any `\addplot` commands causes a problem

pgfplotstodo.tex:3544

Bug [open, Priority 1, Epic “] the axis line combination styles can't be adjusted for 3D because they are evaluated too early.

pgfplotstodo.tex:3741

Bug [open, Priority 1, Epic “] there are a lot of `.code 2 args` styles which do not support spaces between their arguments. Fix this.

pgfplotstodo.tex:3818

Bug [open, Priority 1, Epic “] the `'/pgfplots/table/.search also'` is overwritten during `\addplot table with /search also=/pgfplots`. That's not so good.

pgfplotstodo.tex:4057

Bug [open, Priority 1, Epic ‘]

In 3D case axis [xyz] line != box, there is just ONE hyperplane. My implementation works only if either ALL are box or ALL are 'middle'.

pgfplotstodo.tex:4092

Bug [open, Priority 1, Epic ‘]

javascript stuff does not work if the complete figure is rotated (sidewaysfigure).

pgfplotstodo.tex:4107

Bug [open, Priority 1, Epic ‘]

javascript: incompatibility with external library: 1. filenames: `\jobname` contains characters with incompatible catcodes and that funny `insdljs` package tries to assemble macros with these characters. \rightsquigarrow fixed; I simply use `pgfplotsJS` as temporary file name. 2. the images as such have corrupted forms \rightsquigarrow Can be fixed if `\usepackage{eforms}` is used BEFORE loading `pgf`. The reason: `\begin{Form}` and the shipout-hackery of the `pgf` externalization bite each other. `\begin{Form}` must come before the shipout hackery of `pgf`. 3. `\includegraphics` does not preserve PDF forms.

pgfplotstodo.tex:4114

Bug [open, Priority 1, Epic ‘]

the interrupt bounding box feature should still update the data bounding box. Otherwise, transformations may fail.

6 Feature Proposals PGFPlots

pgfplotstodo.tex:4445

Bug [open, Priority 5, Epic ‘]

Unbounded point meta data should be filtered out.

<http://tex.stackexchange.com/questions/164250/pgfplots-surf-plot-dont-draw-nan?lq=1>

However, it seems as if this “filter out” should not be done as for coordinates (which would filter out all adjacent patch segments). It should merely filter out the current one.

pgfplotstodo.tex:6325

Feature Proposal [open, Priority 6, Epic ‘]

It is certainly possible to write some sort of CELL-BASED 'mesh/surf' shader - a combination of 'flat corner' and cell based rectangles:

- every coordinate denotes a CELL instead of a corner,
- the "shader" maps the `cdata` into the `colormap` to determine the cell color

- details?
 - to get well-defined cells, I have to enforce either a non-parametric lattice grid or do a LOT of additional operations (?).
 - alternative: define N*M cells by N+1 * M+1 points.
 - perhaps a combination of both? \rightsquigarrow that's more or less the same as 'flat mean' up to the further row/column pair
- it would be generally useful to have an "interval" or "cell" mode: the idea is that every input coordinate defines an interval (1d) or a cell (2d). To define the last cell, one needs to add one "mesh width" somehow. I just don't know where:
 - the artificial cell should be processed with the normal streams - including limit updates, stacking etc.
 - the artificial cell needs to know when the end-of-stream occurs. For 1d plots, that may be possible. For 2D plots, this information requires a valid 'cols' key.
 - I suppose it would be best to patch @stream@coord.. at least for the 'cell' mode.
 - Idea:
 - * the `\pgfplots@coord@stream@coord` implementation realizes the cell-mode: after every 'cols' coordinate, a further one is replicated. This needs the "last mesh width". Furthermore, it needs to accumulate a row vector, the "last row". This last row is need during `stream@end` to replicate the further row:
 - * the `\pgfplots@coord@stream@end` implementation has to realize the last step of cell mode: the replication of a further row. It also has to realize the implementation of 'interval' mode (replication of last coordinate). My idea is to simply use an `applist` for this row accumulation. The format should be compatible with `\pgfplots@coord@stream@foreach@NORMALIZED`. That doesn't produce problems, even when the end command is invoked within a `foreach@NORMALIZED` loop - because the loop has already ended.

pgfplotstodo.tex:4129

Feature Proposal [open, Priority 5, Epic “]

allow a simple way to connect coordinates of different axes, i.e. something like `(axis1 cs:1,1) -- (axis 2 cs:3,4)` (Tim Esser, per Mail Apr. 28, 2015)

pgfplotstodo.tex:4133

Feature Proposal [open, Priority 5, Epic “]

add `enlarge limits=to next tick label`, see <http://tex.stackexchange.com/questions/229551/enlarge-limits-to-nearest-tick>

pgfplotstodo.tex:4166

Feature Proposal [open, Priority 5, Epic ‘]

allow # inside of inline tables: the following does not work in any pgfplots version:

```
\documentclass{standalone}
\usepackage{pgfplots}
\pgfplotsset{%
    compat=newest,
}
\begin{document}
\begin{tikzpicture}
\begin{axis}[
    % point meta=explicit symbolic,
]
\addplot table[x index={1}, y expr=\coordindex, header=false, meta index={0}] {
#Re 750 K
"i" 62.099
"i" 62.046
"i" 56.304
"i" -44.258
"2" -28.826
"i" 18.740
"i" -14.653
"i" 14.402
"i" -12.907
"i" 12.295
};
\end{axis}
\end{tikzpicture}
\end{document}
```

pgfplotstodo.tex:4176

Feature Proposal [open, Priority 5, Epic ‘]

write a script which applies the entire “release todo” over night:

- clone into tmp repo, compile manual from scratch with latest PGF
- clone into different tmp repo, compile tests against latest PGF
- same for all supported PGF versions
- improve reporting somehow (log files and summaries somewhere)

pgfplotstodo.tex:4182

Feature Proposal [open, Priority 5, Epic ‘]

stream plots: contour plots in which each contour line is actually of type `mesh` with a specific value of `point meta`

<http://stackoverflow.com/questions/8296617/how-to-plot-a-streamlines-when-i-know-u-and-v-components-of-velocitynumpy-2d>

pgfplotstodo.tex:4188 **Feature Proposal** [open, Priority 5, Epic ‘’]
#30 Legend entries from different plots in groupplot
<https://sourceforge.net/p/pgfplots/feature-requests/30/>

pgfplotstodo.tex:4194 **Feature Proposal** [open, Priority 5, Epic ‘’]
feature-requests:#41 RFE: Add every quiver plot style key
<https://sourceforge.net/p/pgfplots/feature-requests/41>

pgfplotstodo.tex:4198 **Feature Proposal** [open, Priority 5, Epic ‘’]
lua backend support for `restrict expr to domain`

pgfplotstodo.tex:4213 **Feature Proposal** [open, Priority 5, Epic ‘’]
feature-requests:#42 Option for automatic trigonometric axis (ticks and labels)
I suppose the underlying request would be to plug in strategies to determine tick positions combined with a suitable formatter

pgfplotstodo.tex:4337 **Feature Proposal** [open, Priority 5, Epic ‘’]
improve the outcome of `log ticks with fixed point` if the data range is of order $O(1)$.

Hi Benjamin Voigt,

thanks for the detailed email!

A appreciate the level of detail for this feature request, and I am glad that my package p

You asked for preferences: if possible, I always prefer reduced (optimally: minimal) examp

The feature request(s) are, of course, closely related. The overall theme is "improve log t

I believe I understand most of them, although I would need to think through it more carefu

First, let me make some small comments.

1. I believe the requirement list for an algorithm which chooses tick positions + labels i

- generate tick labels automatically
- make it clear that they are in log format
- ensure that there are enough tick labels to fill the axis
- the algorithm has to work reasonably on *every* possible order of magnitude
- ensure that the tick labels have some commonly recognized form

You see that I made rather abstract formulations. The current implementation in pgfplots w
 $10^{-3}, 10^{-2}, 10^{-1}, 10^0$
 $10^{-3}, 10^0, 10^3, 10^6$
 $10^{-1.3}, 10^{-1}, 10^{-0.7}, 10^{-0.3}, 10^0$
 addresses these issues using the standard exponential notation.

Why do I say that? Well, improving the quality of log ticks with fixed point for $O(1)$ numb

2. This is really just a side note: you may want to take a look at the existing key "log i
 There is also some tick fine tuning in section "4.15.4 Tick Fine-Tuning" (the number may v

3. The current tick placement algorithm has no predefined lists of real numbers. It operat

My current priorities in the development of pgfplots are as follows:
 Release 1.11 is the current public stable.

Release 1.12 will have the theme "scalability and performance". It will come with a new ba

Release 1.13 (or whatever it will be called) will probably become a feature release to add

I typically take six months per release; and 1.12 is planned for end of this year. That me

The effort as such is probably quite low; it's just that I have to make a strong focus to

In other words: if you are willing to invest time on this special project, I would be will

Entry points would be <http://tex.stackexchange.com/questions/12668/where-do-i-start-latex->

I will copy this email to my todo list (I assume your suggestions and thought in this mail

What do you think?

Kind regards

Christian

PS

Your name sounds like german origins - or some other european country. Do you come from he

Am 26.10.2014 04:08, schrieb richardvoigt@gmail.com:

>

> Hi Dr. Feuersnger,

>

> To being with, thanks *very* much for all the hard work you've done on pgfplots already,
>
> This is related to the Tex.SE post "pgfplot log axis more than one tick label per decade"
> <http://tex.stackexchange.com/questions/208891/pgfplot-log-axis-more-than-one-tick-label>
>
> Great idea moving to email, among other advantages I can share unredacted pieces of my t
>
> My suggestion is that the following sets of labels be made available:
>
> $10^{-3}, 10^{-2}, 10^{-1}, 10^0$ current default
> $10^{-3}, 10^0, 10^3, 10^6$ current default, when range is huge
>
> 0.001, 0.01, 0.1, 1 currently gotten from "log ticks with fixed point"
> 0.1, 1, 10, 100, 1000 currently gotten from "log ticks with fixe
> 0.1, 0.2, 0.5, 1, 2, 5 given in my Tex.SE answer
> 0.001, 0.002, 0.005, 0.01, 0.02 given in Tex.SE answer
> 50, 100, 200, 500, 1000, 2000 given in Tex.SE answer
> 0.001, 0.003, 0.01, 0.03, 0.1, 0.3, 1 can use technique from Tex.SE answer
> 10, 30, 100, 300, 1000, 3000 can use technique from Tex.SE answer
>
> $10^{-1.3}, 10^{-1}, 10^{-0.7}, 10^{-0.3}, 10^0$ use technique from Tex.SE answer, removing "1
>
> $1\mu, 2\mu, 5\mu, 10\mu, 20\mu, 50\mu, 100\mu$ this would be nice, for values where "log
> 100k, 200k, 500k, 1M, 2M, 5M, 10M same
> 1m, 1, 1k, 1M same, when range is huge
>
> $1 \cdot 10^{-6}, 2 \cdot 10^{-6}, 5 \cdot 10^{-6}, 1 \cdot 10^{-5}, 2 \cdot 10^{-5}$
> maybe call this "log ticks with integer exponent"
> $1 \cdot 10^{-6}, 3 \cdot 10^{-6}, 1 \cdot 10^{-5}, 3 \cdot 10^{-5}, 1 \cdot 10^{-4}, 3 \cdot 10^{-4}$
> same idea, wider range
>
> Since the magnitude of my data is reasonably close to 1, I prefer the second group, and
>
> I just don't like fractional exponents. In my mind, log plots are for presenting data w
>
> I also don't have to let my data get far away from zero, because I can label my axis as
>
> But I realize that other people may see their data differently, or work with different d
>
> As you commented, there really are two discrete things here: tick placement, and label f
>
> I propose something like "log rational ticks" to switch to whichever of 1-10, 1-3-10, 1-2-
>
> And then formats of default (mantissa = 1 always, exponent varies), "log ticks with fixe
>
> It seems like pgfplots has a lot of customization points with a path of tag/.code I don
>
> Again, thanks for the awesome work that is pgfplots 1.9. When I say that "I doubt anyone
>
> R Benjamin Voigt

>

pgfplotstodo.tex:4343

Feature Proposal [open, Priority 5, Epic ‘]

Add support for a transformation which allows TIME input data (i.e. without date)

see <http://tex.stackexchange.com/q/79252/18401>

pgfplotstodo.tex:4352

Feature Proposal [open, Priority 5, Epic ‘]

slanted and sloped text (projected onto some axis plane)

see <http://tex.stackexchange.com/questions/212699/text-projection-onto-plane-in-3d-pgf-plots>

this also has math formulas to set up the trafo

pgfplotstodo.tex:4358

Feature Proposal [open, Priority 5, Epic ‘]

external lib: rerun externalization in case of unresolved references.

see

<http://www.texwelt.de/wissen/fragen/9476/labels-an-pgfplots/9527>
for a sketch and use-case

pgfplotstodo.tex:4374

Feature Proposal [open, Priority 5, Epic ‘]

allow some simply style of sorts “xtick should have a distance of 10. Get it done.”

pgfplotstodo.tex:4382

Feature Proposal [open, Priority 5, Epic ‘]

add styles to format seconds using some time format

see <http://tex.stackexchange.com/questions/198706/convert-gnuplot-script-to-pgfplots-using-raw-gnuplot-option>

see <http://tex.stackexchange.com/questions/118676/increasing-dateplots-resolution-to-seconds/219447#219447>

- pgfplotstodo.tex:4390 **Feature Proposal** [open, Priority 5, Epic ‘']
 get in touch with the author of the colorbrewer styles on
<http://www.traag.net/2014/06/05/281/>
 these colors look better than the current default
 see <http://tex.stackexchange.com/questions/119161/pre-defined-color-cycles-%C3%A0-la-r-colorbrewer>
- pgfplotstodo.tex:4396 **Feature Proposal** [open, Priority 5, Epic ‘Usability’]
 parse elements of tick positions with math parser
<http://tex.stackexchange.com/questions/187115/with-pgfplots-how-to-manually-enter-ticks-as-fractions>
- pgfplotstodo.tex:4402 **Feature Proposal** [open, Priority 5, Epic ‘']
 table package: Add style “modify content for the following row indices”
 can be copy-pasted from
<http://tex.stackexchange.com/questions/187067/how-to-have-different-colormaps-for-different-columns-in-the-same-heatmaps-table/187099#187099>
- pgfplotstodo.tex:4410 **Feature Proposal** [open, Priority 5, Epic ‘']
 fillbetween: accept `soft path={inner x range}` or something like that,
 compare http://tex.stackexchange.com/questions/180127/stacking-plots-in-animation-using-fill-between-library-with-dynamic-calculation/180299?noredirect=1#comment416484_180299
- pgfplotstodo.tex:4416 **Feature Proposal** [open, Priority 5, Epic ‘']
 allow predicates styles of sorts `every intersection below y={0}` *or, even better: every lower intersection segment* – after all, “upper” and “lower” can be identified by means of scalar productions with same directed vector. The directed vector can be plugged in from the axis → think about solutions
 see http://tex.stackexchange.com/questions/207042/pgfplots-addplot-color-depending-on-sign/207157#comment535403_207157
- pgfplotstodo.tex:4432 **Feature Proposal** [open, Priority 5, Epic ‘']
 ich bin es nochmal. Ich habe nochmal eine Anmerkung zu den decorations. Ich bin gerade dabei, meine Plots mit Pfeilen zu versehen wie ich es in dem Bild

zuvor bereits getan habe. Leider kann ich für die decorations nur folgende Angabe machen:

```
mark = at position 0.15 with {\arrow [scale=1]{stealth}},
```

Jedoch kommt es bei Kurven häufiger vor, dass ich nicht gut abschätzen kann, ob es sich dabei um Position 0.1 oder 0.15 oder dergleichen handelt. Ich habe es so verstanden, dass der Compiler die Strecke der Kurve vermisst und bei bspw.

```
mark = at position 0.5 with {\arrow [scale=1]{stealth}},
```

eine Dekoration bei der Hälfte der Kurve macht. Doch wo ist die Hälfte der Kurve, wenn diese gekrümmt und gewunden ist? Nun ist es umständlich immer diese Dekorationen anzupassen und ich würde lieber eine x oder y Koordinate verwenden und sagen können:

```
mark = at x position 40 with {\arrow [scale=1]{stealth}},
```

So kann ich mir sicher sein, dass der Pfeil dann der x-Koordinate 40 zugeordnet wird und auf der Kurve landet.

pgfplotstodo.tex:4436 **Feature Proposal** [open, Priority 5, Epic ‘']
Implement something like `pos={x=40}`

pgfplotstodo.tex:4452 **Feature Proposal** [open, Priority 5, Epic ‘']
addplot graphics: support “scale to natural dimensions” of the input graphics

there is a half-ready solution in
<http://tex.stackexchange.com/questions/175618/addplot-graphics-maintaining-images-aspect-ratio-despite-different-scaling-of-175726#175726>

pgfplotstodo.tex:4525 **Feature Proposal** [open, Priority 5, Epic ‘Usability’]
The distinction into survey phase and visualization phase is technically reasonable, but causes confusion.

Is there a way to simplify loop operations during the survey phase as in
<http://tex.stackexchange.com/questions/172917/pgfplots-and-using-axis-cs-to-add-points> ?

pgfplotstodo.tex:4535 **Feature Proposal** [open, Priority 5, Epic ‘Usability’]
Pgfplots requires user input to distinguish between parameterized 3d plots and matrix-like 3d plots.

Why can't PGFPlots determine automatically if `z buffer=sort` is adequate?

<http://tex.stackexchange.com/questions/172753/pgfplots-and-gnuplot-with-addplot3>

ATTENTION: what about 3d sampled line plots!? this would break with `z buffer sort`.

pgfplotstodo.tex:4565

Feature Proposal [open, Priority 5, Epic 'Usability']

pgfplots math expressions always yield internal FPU formats which confuses users.

Return SCI representation instead.

TO BE CLARIFIED: which operations should be replaced? REplacing 'x filter' and its friends might actually make things worse because FPU functions will no longer accept the argument.

It might be useful to improve the FPU such that `declarefunction` for a function which does *not* expect FPU arguments accept it.

This could be done by patching `\pgfmath@stack@push@operation` - and check if the argument is a function and that function has a known FPU implementation (its float-backup exists). If not: generate a dummy which converts to fixed points. Use the function's arity!

see

<http://tex.stackexchange.com/questions/171263/plotting-a-function-defined-with-pgfmathdecl>

see

<http://texwelt.de/wissen/fragen/3960/fraktale-mit-pgfplots?Seite=1#3993>

I started to work on a solution for the second one, see the uncommented call to `\pgfplots@expression@normalize@floats`

pgfplotstodo.tex:4590

Feature Proposal [open, Priority 5, Epic '']

bullet graphs:

<http://tex.stackexchange.com/questions/146538/how-to-create-vertical-bullet-graphs-with-pstricks>

Inspiration:

<http://img35.imageshack.us/img35/1061/snap2134.png>

I started a prototype. To do items:

- make sure that color schemes can be exchanged in a simple way
- prepare the package for up to 3 discriminative markers
- regarding data files: TO CLARIFY

branch ‘bulletplots’

perhaps this would be a good contribution together with
<http://tex.stackexchange.com/questions/29293/is-there-a-package-that-provides-graphing-in-the-style-of-ed-tufte/29311#29311>

pgfplotstodo.tex:4596

Feature Proposal [open, Priority 5, Epic ‘’]

Given some PGF point, allow to access the high-level coordinates.

see <http://tex.stackexchange.com/questions/174404/convert-unit-to-coordinate-works-for-x-coordinate-but-not-for-y-coordinate/174443#174443> for a use-case and note that there is a work-around which works for ‘pin’ in the pgfplots manual - and that is awkward.

pgfplotstodo.tex:4602

Feature Proposal [open, Priority 5, Epic ‘’]

add “stackable tick labels” (tick labels with vertical shifts if they are too close).

compare <http://tex.stackexchange.com/questions/164673/positioning-even-or-odd-x-axis-tick-labels-in-pgfplots>

pgfplotstodo.tex:4606

Feature Proposal [open, Priority 5, Epic ‘’]

bar plots: Introduce significance stars (see GROUP BARS on page 81)

pgfplotstodo.tex:4880

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

GROUP BARS

Bar plots: simplify grouped bars

Hi Joshua,

as already mentioned, your old mails from January have slipped my discipline... I am sorry

You asked for a simpler way to

- a) position groups of bars without having to compute ‘bar shift’ manually
- b) a simpler way to get "significance stars".

First, grouped bar charts are an open feature request in pgfplots, and your input will even

The first request is actually possible, assuming that you always provide them in the sequence

The default is

```
/pgfplots/ybar/.style={
  /pgf/bar shift={%
    % total width = n*w + (n-1)*skip
    % -> subtract half for centering
    -0.5*(\numplotsofactualtype*\pgfplotbarwidth + (\numplotsofactualtype-1)*#1},%
    % the '0.5*w' is for centering
    (.5+\plotnumofactualtype)*\pgfplotbarwidth + \plotnumofactualtype*#1},%
}
```

and my modification substitutes every index and 'n' by half of it:

```
\pgfplotsset{
  % #1 = separation between bars
  bar shift for half number plots/.style={%
    /pgf/bar shift={%
      % total width = n*w + (n-1)*skip
      % -> subtract half for centering
      -0.5*(\numplotsofactualtype/2*\pgfplotbarwidth + (\numplotsofactualtype/2-1)*#1},%
      % the '0.5*w' is for centering
      (.5+div(\plotnumofactualtype,2))*\pgfplotbarwidth + div(\plotnumofactualtype,2)*#1},%
    },%
  },%
  bar shift for half number plots/.default=2pt,
}
```

With this definition, you do not have to write 'bar shift' in your styles.

The whole figure becomes

```
\usemodule[pgfplots]
\pgfplotsset{compat=newest}

\pgfplotsset{HeartControl/.style={
  {
    red, fill=red!33!white,
    %bar shift=-0.1667
  }
}}
\pgfplotsset{HeartDiabetes/.style={
  {
    red!33!black, fill=red!66!white,
    %bar shift=+0.1667
  }
}}
\pgfplotsset{KidneyControl/.style={
  {
```

```

        orange, fill=orange!33!white,
        %bar shift=-0.1667
    }}
\pgfplotsset{KidneyDiabetes/.style=
{
    orange!33!black, fill=orange!66!white,
    %bar shift=+0.1667
}}

\pgfplotsset{/pgfplots/ybar legend/.style=
{
    /pgfplots/legend image code/.code={%
        \draw[
            ##1, /tikz/.cd,
            bar width=0.25em,
            yshift=-0.27em,
            bar shift=0pt
        ]
        plot coordinates {(0pt,0.8em)};
    }
}}

\pgfplotsset{
    % #1 = separation between bars
    bar shift for half number plots/.style={%
        /pgf/bar shift={%
            % total width = n*w + (n-1)*skip
            % -> subtract half for centering
            -0.5*(\numplotssofaractualtype/2*\pgfplotbarwidth + (\numplotssofaractualtype/2-
            % the '0.5*w' is for centering
            (.5+div(\plotnumofactualtype,2))*\pgfplotbarwidth + div(\plotnumofactualty
        },%
    },%
    bar shift for half number plots/.default=2pt,
}

\starttext

\starttikzpicture
\startaxis
[
    bar width=0.3,
    ybar,
    bar shift for half number plots=5pt,
    xtick=data,
    ylabel={mRNA level},
    ymin=0,
    xmin=0.333, xmax=2.667,
    xtick={1,2}, xticklabels={Heart,Kidney},
    error bars/y dir=both,

```

```

        error bars/y explicit,
        legend columns=2,
        legend pos=outer north east,
        legend cell align=left
    ]

    \addplot+[HeartControl] coordinates {(1,1) +- (0,0.1)};
    \addplot+[KidneyControl] coordinates {(2,1) +- (0,0.12)};
    \addplot+[HeartDiabetes] coordinates {(1,1.1) +- (0,0.2)};
    \addplot+[KidneyDiabetes] coordinates {(2,0.8) +- (0,0.05)};

    \draw (axis cs:2,1.15) +(-2.2em,0) -- +(2.2em,0);
    \node[anchor=south, yshift=-1ex] at (axis cs:2,1.15) {*};

    \legend{{\kern-0.1em}, Control, {\kern-0.1em}, Diabetes}

    \stopaxis
\stoptikzpicture

\stoptext

```

I suppose you could even simplify the styles by means of a cycle list or whatever.

I also experimented with symbolic x coords, but how would you write "xmin=0.3333" or "bar

You can use

```

\def\heartUnit{1}
\def\kidneyUnit{2}

```

to introduce constants - this might make it more readable.

I am aware of the fact that this solution comes way too late. Perhaps it proves to be useful

Kind regards

Christian

Am 21.01.2014 13:29, schrieb Joshua Krmer:

> Dear pgfplots developers!

>

> First, thanks a lot for your great package. I'm using it to create

> diagrams in ConTeXt. Please consider the following (M)WE. I hope you

> can run it, otherwise, you can see the output here:

> <http://666kb.com/i/cl5sdm34i4ig69mkk.png>

```

>
> \usemodule[pgfplots]
> \pgfplotsset{compat=newest}
>
> \pgfplotsset{HeartControl/.style=
> {
> red, fill=red!33!white,
> bar shift=-0.1667
> }}
> \pgfplotsset{HeartDiabetes/.style=
> {
> red!33!black, fill=red!66!white,
> bar shift=+0.1667
> }}
> \pgfplotsset{KidneyControl/.style=
> {
> orange, fill=orange!33!white,
> bar shift=-0.1667
> }}
> \pgfplotsset{KidneyDiabetes/.style=
> {
> orange!33!black, fill=orange!66!white,
> bar shift=+0.1667
> }}
>
> \pgfplotsset{/pgfplots/ybar legend/.style=
> {
> /pgfplots/legend image code/.code={%
> \draw[
> ##1, /tikz/.cd,
> bar width=0.25em,
> yshift=-0.27em,
> bar shift=0pt
> ]
> plot coordinates {(0pt,0.8em)};
> }
> }}
>
> \starttext
>
> \starttikzpicture
> \startaxis
> [
> ybar,
> xtick=data,
> ylabel={mRNA level},
> ymin=0,
> xmin=0.333, xmax=2.667,
> xtick={1,2}, xticklabels={Heart,Kidney},
> error bars/y dir=both,

```

```

> error bars/y explicit,
> bar width=0.3,
> legend columns=2,
> legend pos=outer north east,
> legend cell align=left
> ]
>
> \addplot+[HeartControl] coordinates {(1,1) +- (0,0.1)};
> \addplot+[KidneyControl] coordinates {(2,1) +- (0,0.12)};
> \addplot+[HeartDiabetes] coordinates {(1,1.1) +- (0,0.2)};
> \addplot+[KidneyDiabetes] coordinates {(2,0.8) +- (0,0.05)};
>
> \draw (axis cs:2,1.15) +(-2.2em,0) -- +(2.2em,0);
> \node[anchor=south, yshift=-1ex] at (axis cs:2,1.15) {*};
>
> \legend{{\kern-0.1em}, Control, {\kern-0.1em}, Diabetes}
>
> \stopaxis
> \stoptikzpicture
>
> \stoptext
>
> As you can see, I have two groups (organs: hearts, kidneys), sometimes
> more, and two conditions (control, Diabetes). To make it easier to
> compare the diagrams (there are many), I want to use consistent colours
> for the same organs, and two brightnesses for the two conditions. The
> code above works, but automatic positioning would be much nicer, so I
> could just set something like "bar width=..." and "bar separation=..."
> and let the bars be positioned automatically. This would also allow me
> to use symbolic coordinates, avoiding the pseudo coordinates (1 and
> 2). Is there a better way to get the desired result than what I've
> done?
>
> I also hope there is a better way to create significance stars. If two
> values are significantly different, there is a horizontal line to be
> added which spans the two bars, and a symbol above it. The symbols
> usually are one till three stars (depending on the degree of
> significance), sometimes other symbols are used in the literature. At
> least it would be nice if I could define the coordinates for the
> horizontal line with something like "max(errormark1, errormark2) +a",
> ie, the higher of the two error marks involved plus some separation.
>
> Kind regards,
> Joshua Krmer
>
>
> -----
> CenturyLink Cloud: The Leader in Enterprise Cloud Services.
> Learn Why More Businesses Are Choosing CenturyLink Cloud For

```

```

> Critical Workloads, Development Environments & Everything In Between.
> Get a Quote or Start a Free Trial Today.
> http://pubads.g.doubleclick.net/gampad/clk?id=119420431&iu=/4140/ostg.clktrk
> -----
> Pgfplots-features mailing list
> Pgfplots-features@lists.sourceforge.net
> https://lists.sourceforge.net/lists/listinfo/pgfplots-features

```

pgfplotstodo.tex:4914

Feature Proposal [open, Priority 5, Epic “]

suppress tick-line cross in 3d for view directions in which the cross degenerates to a very thick line

compare

```

\documentclass[tikz,12pt]{standalone}
\usepackage{tikz,pgfplots,pgfplotstable}

\pgfplotsset{compat=1.10}

\pgfplotsset{every axis/.append style={tick style={line width=0.7pt}}}

\pgfplotstableread{
a b
-0.1 0.2
0.1 0.5
}\testdata

\begin{document}
\foreach \h in {5,10,...,360} {
\begin{tikzpicture}

\begin{axis}[title=\h,axis lines=center, ymin=-0.22,ymax=0.22, xmin=-0.2,xmax=0.2,xlabel=x
\addplot3 [color=blue,] table[x expr=0,y=a,z=b] {\testdata};
\end{axis}

\end{tikzpicture}
\par
}

\end{document}

```

pgfplotstodo.tex:4931

Feature Proposal [open, Priority 5, Epic “]

Tufte-style range frames for 3d <http://tex.stackexchange.com/questions/165766/tufte-style-range-frames-for-three-dimensional-plots>

pgfplotstodo.tex:4937

Feature Proposal [open, Priority 5, Epic ‘’]

Add option of sorts “shift along outer normal vector of current axis” while generating paths for axes, ticks, tick labels, and perhaps even grid lines.

<http://tex.stackexchange.com/questions/165766/tufte-style-range-frames-for-three-dimensional-plots>

pgfplotstodo.tex:4947

Feature Proposal [open, Priority 5, Epic ‘’]

Allow to shift (x) tick labels vertically if they are too dense.

Sometimes one needs lots of tick labels. It would be cool if every second would be shifted vertically, perhaps with an edge to the original location

pgfplotstodo.tex:4985

Feature Proposal [open, Priority 5, Epic ‘’]

the ... syntax in tick label position lists is inherently limited to `[-16384,16384]` (it inherits the limitations of `\foreach`). Think about alternatives

pgfplotstodo.tex:5021

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

It is surprisingly difficult to have JUST axis ticks and tick labels and labels, but NO axis line. This is because I accidentally made `axis x line=none` equivalent to `hide x axis`. Too bad.

Idea: implement keys `axis x line hidden=true,false`. Perhaps with options `axis x line=bottom hidden` which is the same as `axis x line hidden,axis x line=bottom?`

pgfplotstodo.tex:5042

Feature Proposal [open, Priority 5, Epic ‘’]

Implement document-level javascript for the clickable lib WITHOUT the `eforms/insdljs` package

should be quite straight-forward. Unless resource-acquisition problems occur (i.e. interoperability issues with other packages)

See

<http://tex.stackexchange.com/questions/3080/what-is-the-best-way-to-insert-document-level-javascript-in-latex-documents?rq=1>

pgfplotstodo.tex:5048

Feature Proposal [open, Priority 5, Epic ‘']

Implement a custom legend environment such that one doesn't need to collect all options manually

<http://tex.stackexchange.com/questions/54794/using-a-pgfplots-style-legend-in-a-plain-old->

pgfplotstodo.tex:5053

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

feature-requests:#43 Option to set the BaseValue of a bar plot

<https://sourceforge.net/p/pgfplots/feature-requests/43/>

pgfplotstodo.tex:5058

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

Allow 3d bar plots (see also <http://tex.stackexchange.com/questions/176347/2d-bar-chart-in-3d-space/176363#176363>)

pgfplotstodo.tex:5070

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

Individual bars: allow to modify / adjust the bar plot handler(s) such that each bar can have its individual appearance

- create individual `\path` instructions for every bar
- discard the outer `\path` at the end
- allow simple styles of sorts `bar 1/.style={...}` or `bar value 1.23/.style={...}` perhaps using prefix search? similar to the request for nodes near coords
- should be dependent on point meta (like scatter plots)

There is some preparation key `at begin bar` combined with `at end bar` in the bar plot handlers. It can be used as low-level backend, but it still needs to be worked out (see `unittest_bar_shade_atbeginbar.tex`)

pgfplotstodo.tex:5074

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

nodes near coords: allow styles of sorts `node near coord 1/.style={...}` or `node near coord value 1.23/.style={...}` (similar to the feature request for bar plots)

pgfplotstodo.tex:5080

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

bar plots: auto-select axis limits, unit size, bar width, and bar shift.

Perhaps it is sufficient to auto-select bar width.

- pgfplotstodo.tex:5084 **Feature Proposal** [open, Priority 5, Epic 'Bar plots']
Is it possible to have bar plots which do not start from the x or y axis?. For example a bar plot from (0,2) to (0,3).
- pgfplotstodo.tex:5088 **Feature Proposal** [open, Priority 5, Epic 'Bar plots']
bar plots: provide constant zero level?
- pgfplotstodo.tex:5096 **Feature Proposal** [open, Priority 5, Epic '']
allow to rotate polar plots and fix rotation of tick labels.

see

<http://tex.stackexchange.com/questions/116830/polar-plot-x-and-y-ticks-and-units>
- pgfplotstodo.tex:5101 **Feature Proposal** [open, Priority 5, Epic 'Bar plots']
polar axes: polar bar plots (see sourceforge feature request and http://matplotlib.sourceforge.net/examples/pylab_examples/polar_bar.html)
- pgfplotstodo.tex:5111 **Feature Proposal** [open, Priority 5, Epic 'Bar plots']
discontinuity in the middle of a plot (as an example see the phase diagram of water http://pruffle.mit.edu/3.00/Lecture_29_web/img20.gif)

<http://peltiertech.com/images/2011-11/Ybroken.png>

<http://tex.stackexchange.com/questions/46422/axis-break-in-pgfplots>
- pgfplotstodo.tex:5115 **Feature Proposal** [open, Priority 5, Epic 'Bar plots']
chunked bars: interrupt the bars at predefined coordinates (like white grid lines)
- pgfplotstodo.tex:5126 **Feature Proposal** [open, Priority 5, Epic 'Bar plots']
bar plots:
 - bar interval plot handler which *assumes* uniform distances. This allows to eliminate the last, superfluous grid point (because it can be generated automatically as replication $xlast + h$ for known h)

- in fact, I could also implement `xlast + hlast` and introduce a new name like `'bar interval*'` or something like that

pgfplotstodo.tex:5138

Feature Proposal [open, Priority 5, Epic 'Bar plots']

Mails from Stefan Ruhstorfer:

- Gruppierte Säulendiagramme sind nach meinem Wissenstand nur dann möglich wenn man in der Axis-Definiton die Bedingung `ybar` angibt. Ich finde diese Ausrichtung sehr unflexible, da ich sehr oft über das Problem stolpere, dass ich in meinem gruppierten Säulendiagramm noch eine waagrechte Linie oder ähnlichs einzeichnen möchte um z.B. meine obere Toleranzgrenze einzuzeichnen. Bis jetzt mache ich das über den normalen `draw` Modus, was auch ausgezeichnet funktioniert. Jedoch habe ich dann das Problem, dass ich keinen schönen Legendeintrag mehr bekomme. Hier hätte ich 2 Vorschläge. Zum einen die Legende "freier" zu gestalten. Also so, dass man beliebig (ggf. auch ohne Plot) ein Legendenelement hinzufügen kann und vllt. noch das zugehörige Symbol festlegen kann. (Bis jetzt habe ich das Problem, das ich mit tricksen zwar meine Obere Toleranzgrenze in die Legende bekomme, dann jedoch mit einem Säulenzeichen davor). Der andere Vorschlag ist, dass Säulendiagramm anders zu definiern. So das ich auch noch einen Plot hinzufügen kann, der mir eine waagrechte Linie ohne zu tricksen einzeichnen lässt.
- Eine Gruppierung von stacked bars ist nach meinem Wissen nicht möglich. Es ist zwar schwer sich ein Anwendungsgebiet dafür vorzustellen, aber wenn sie danach mal suchen (speziell im Excelbereich) werden sie sehen, dass viele Leute so eine Funktion benutzen. \rightsquigarrow siehe auch folgemails mit Beispielskizzen \rightsquigarrow beachte: Fall 2.) erfordert mehr arbeit als lediglich `'line legend'`, weil `ybar` ja den koordinatenindex verarbeitet!

pgfplotstodo.tex:5142

Feature Proposal [open, Priority 5, Epic 'Bar plots']

let stacked bar plots respect the line width when stacking them on top of each other

pgfplotstodo.tex:5161

Feature Proposal [open, Priority 5, Epic 'Bar plots']

On input: provide the desired distance between adjacent bars. The bar width should be automatically determined in a way which shows all bars.

An extreme case would degenerate to `ycomb`.

If the plot area does is insufficient, bar distances should be restricted (?)

Note: if (and only if) the bars have unit distance 1, a relative distance is already supported by providing `bar width=0.9` or something like that...

Note: if we knew the distance between adjacent ticks, and we assume that each tick has its associated bar plot, we could define the bar width in terms of the tick distance... perhaps I should expose read-only access to the list of (computed) tick positions; with a convenience method to access the common distance? Or just a common distance?

pgfplotstodo.tex:5167

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

bar plots: if you provide both, the desired distance between adjacent bars and the bar width, the axis limits should be increased or decreased automatically.

This is actually a more generic concept: it would be ‘scale mode=limits only’ (?)

pgfplotstodo.tex:5171

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

Default bar plot styles should always include the (correct) origin in the visible axis range.

pgfplotstodo.tex:5177

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

It should be simpler to customize the position of nodes near coords in a way to position them in the middle or below each bar.

This is particularly difficult for stacked bar plots

pgfplotstodo.tex:5195

Feature Proposal [open, Priority 5, Epic ‘’]

modify the `node[at=<pos>]` feature such that `node[at value=42.4]` or `at max value` or `at min value` or `node[at coordindex=3]`

pgfplotstodo.tex:5202

Feature Proposal [open, Priority 5, Epic ‘’]

Layered graphics: consider drawing tick lines which are on the “outer part” of the axis on the foreground layer.

See

<http://tex.stackexchange.com/questions/31708/draw-a-bivariate-normal-distribution-in-tikz/> for a motivation (the tick lines are hidden by the surface)

pgfplotstodo.tex:5206

Feature Proposal [open, Priority 5, Epic ‘’]

allow support for units in `bar width` and `bar shift` (compare the implementation for circles/ellipses)

pgfplotstodo.tex:5223

Feature Proposal [open, Priority 5, Epic ‘’]

it would be nice to have automatic PNG export for huge graphics. Such an approach, combined with plot graphics, could result in considerably smaller pdfs and faster rendering. At the same time, it would not suffer the limitation which arises if one uses the external lib and converts the complete figure to png (including axis descriptions)

pgfplotstodo.tex:5233

Feature Proposal [open, Priority 5, Epic ‘’]

There is no simple way to provide LOG colorbars:

1. `y mode=log` is not supported in ‘every colorbar’ due to key filtering problems
2. `disablelogfilter` appears to be useless and does not respect ‘log basis’

If those two this would be fixed, one could provide `colorbar style={y mode=log,disablelogfilter}` and would get a proper logarithmic colorbar. Perhaps even combined with `log basis ... ?`

pgfplotstodo.tex:5237

Feature Proposal [open, Priority 5, Epic ‘’]

Cases-statement in math parser

pgfplotstodo.tex:5245

Feature Proposal [open, Priority 5, Epic ‘Bar plots’]

provide a way to provide more customization to stacked plots as in

<http://tex.stackexchange.com/questions/13627/pgfplots-multiple-shifted-stacked-plots-in-on>

(stacked and clustered bar charts)

pgfplotstodo.tex:5249

Feature Proposal [open, Priority 5, Epic ‘’]

the `empty line` feature should produce a log notice when it finds an empty line in compat mode.

pgfplotstodo.tex:5257 **Feature Proposal** [open, Priority 5, Epic ‘’]
Support something like
`\addplot table[x symbolic expr={\thisrow{year}-\thisrow{month}-\thisrow{day}}]`.

pgfplotstodo.tex:5261 **Feature Proposal** [open, Priority 5, Epic ‘’]
What about a ‘draft’ mode which does nothing but typeset an empty axis without descriptions?

pgfplotstodo.tex:5269 **Feature Proposal** [open, Priority 5, Epic ‘’]
Provide features of an axis *outside* of the axis environment. For a start, this could use the `axis cs` (or an alias to it).

Details and examples:

https://sourceforge.net/tracker/?func=detail&atid=1060659&aid=3086794&group_id=224188

pgfplotstodo.tex:5273 **Feature Proposal** [open, Priority 5, Epic ‘’]
add ‘force 2d axis’ key (or similar)

pgfplotstodo.tex:5283 **Feature Proposal** [open, Priority 5, Epic ‘’]
could you extend the `/tikz/prefix` key so it also works as a prefix for imported files/tables? So far one has to type for example
`\addplot table {plots/data/test.txt};`

If there would be a search path like `\graphicspath` for graphics it would be really nice.

See also https://sourceforge.net/tracker/?func=detail&atid=1060659&aid=3020246&group_id=224188

pgfplotstodo.tex:5291 **Feature Proposal** [open, Priority 5, Epic ‘’]
Support standard filters for `hist` and its variants.

Improve filtering for `hist` and similar plot handlers.

I already added the `hist/data filter` and `pre filter` keys (undocumented!). Use them.

- pgfplotstodo.tex:5296 **Feature Proposal** [open, Priority 5, Epic ‘’]
the ‘xtick’ syntax accepts only numbers, not even constant expressions are possible (and ‘pi’ is even more complicated).
- pgfplotstodo.tex:5301 **Feature Proposal** [open, Priority 5, Epic ‘’]
Table Package: support context-based row predicates (some kind of WHERE clauses)
- pgfplotstodo.tex:5305 **Feature Proposal** [open, Priority 5, Epic ‘’]
support the /data point/x method for all key filters and in all contexts (i.e. in the same context where \thisrow is accepted)
- pgfplotstodo.tex:5309 **Feature Proposal** [open, Priority 5, Epic ‘’]
Support selection of individual 3D axis lines which shall be drawn (or “floor”)
- pgfplotstodo.tex:5322 **Feature Proposal** [open, Priority 5, Epic ‘’]
linear regression which passes through (0,0) (see mail of Stefan Pinnow)
- pgfplotstodo.tex:5327 **Feature Proposal** [open, Priority 5, Epic ‘’]
plot graphics 3D: handle the case when the first two points share the same x (or y) coordinate
- pgfplotstodo.tex:5331 **Feature Proposal** [open, Priority 5, Epic ‘’]
hist does not allow modifications to the data range
- pgfplotstodo.tex:5356 **Feature Proposal** [open, Priority 5, Epic ‘Bar plots’]
see the interesting things at
<http://peltiertech.com/Excel/Charts/axes.html#Broken> broken (y) axis:
remove interval [a,b] idea: if $y \geq a$: visualize as usual if $a \leq y < b$: use coordinate $y = a$ if $b \leq y$: use coordinate $y = y - (b - a)$ axis:
- compute two sets of axis descriptions. Perhaps one can try to compute the step size just once, and discard only [a,b] afterwards? This would require to use a canvas axis length corresponding to the unremoved axis range. BTW: I need access to the unremoved axis range; both for tick computation and for ‘nodes near coords’ or the clickable lib.
 - draw a decoration at the break.

- perhaps also a decoration near affected coords.
- perhaps I should apply the thing during the visualization phase, not before. Then, I have all limits and the correct coordinates; only canvas coords are affected.

pgfplotstodo.tex:5365 **Feature Proposal** [open, Priority 5, Epic ‘]

feature to replicate axis descriptions on both sides

pgfplotstodo.tex:5372 **Feature Proposal** [open, Priority 5, Epic ‘]

couldn't you add something like `\providecommand*\pgfplotsset[1]{}` to the "tikzexternal.sty" so one doesn't have to do it by hand when switching from tikz/pgfplots?

pgfplotstodo.tex:5442 **Feature Proposal** [open, Priority 5, Epic ‘]

Das `pos=` feature funktioniert nur ungenau fuer smooth. Implementiere es genauer.

pgfplotstodo.tex:5447 **Feature Proposal** [open, Priority 5, Epic ‘]

make work `\matrix in \matrix` so one can use groupplots or "Alignment in Array Form" (section 4.18.4) with legends

pgfplotstodo.tex:5475 **Feature Proposal** [open, Priority 5, Epic ‘]

groupplots: group-wide axis labels

pgfplotstodo.tex:5493 **Feature Proposal** [open, Priority 5, Epic ‘]

is there a way to get the current row/col index during `addplot`?

pgfplotstodo.tex:5519 **Feature Proposal** [open, Priority 5, Epic ‘]

plot

shell: - It would be nice if the standard shell interpreter could be replaced. Idea:

`\pgfkeys{/pgfplots/plot shell/interpreter/.code 2 args={sh #1 > #2}}`

then in the code

`\pgfkeysvalueof{/pgfplots/plot shell/interpreter/.cmd}{#1.sh}{#1.out}\pgfeov`

- the `pgfshell` macro is quite general and could be added to `pgf` (as suggested by you, Stefan). However, this would also need modifications in `tikz.code.tex` to get some sort of high-level user interface. I find `plot shell` very useful, and it could be added easily. My suggestion: Either write a high level user interface for `tikz` or rename the command to `pgfplotshell` and put it into

pgfplotscoordprocessing.code.tex. In the meantime, I added it to pgfplotscoordprocessing.code.tex (bottom). - there is a potential difficulty with the 'addplot table shell' command (which is a good solution!): the semicolon in this routine will have a fixed catcode. But packages like babel with french language will change it to active, so french people can't use addplot table shell. The solution is technical and I am not proud of my own anyway... we'll just have to think about one. - documentation for the 'table shell' feature is missing yet. - I am not sure if the replication of /tikz/prefix and /tikz/id is helpful or confusing...

pgfplotstodo.tex:5537

Feature Proposal [open, Priority 5, Epic “]

new `\plotnumofactualtype` thing: if you set /tikz/ plot handlers in `\begin{axis}`, they won't be set before the visualization phase. consequently, I can't count them! Idea: add a 'family' to each of them. Or write a coord filter which checks for `\tikz@plot@handler`. Or write pgfplots styles which set them.

pgfplotstodo.tex:5662

Feature Proposal [open, Priority 5, Epic “]

polar:

- is my current datascaling approach correct? I mean, is the linear trafo feasible at all?
- the `*affine*` radius `datascaletrafo` could be enabled, if only parts of the circle are drawn at all, for example `xmin=0,xmax=45,ymin=1e-4,ymax=1.003e-4` Idea: check arc size and disable the radius `*affine*` data scaling only if the arc has more than 90 (?) degrees Is that mathematically correct? And: is it useful at all?
- handle "empty axis". It should reset to a circle, not a box.

pgfplotstodo.tex:5666

Feature Proposal [open, Priority 5, Epic “]

patch visualization: provide displacement input format

pgfplotstodo.tex:5698

Feature Proposal [open, Priority 5, Epic “]

the following keys should process their argument with `pgfmathparse`:

xyz tick,

- min/max
- tickmin/max
- meta min/max

- domain/ y domain,
- error bar arguments,
- without FPU: width/height/ view
- check optimizations of the math parser!
- check if I can activate the FPU during the survey phase!

TODO: check which ones are missing. Some of them have been added in the meantime

pgfplotstodo.tex:5708

Feature Proposal [open, Priority 5, Epic ‘]

Idea for input stuff: implement high level user interface for coordinate input, similar to the pgf basic level framework. Then, add styles on top of it (try to be compatible with DV engine)

pgfplotstodo.tex:5730

Feature Proposal [open, Priority 5, Epic ‘]

new plot structure : use the ‘/data point’ key interface coming with pgf CVS

pgfplotstodo.tex:5808

Feature Proposal [open, Priority 5, Epic ‘]

quiver plots:

- allow to disable update of axis limits
- provide rescaling of arrows such that they don’t overlap. manual rescaling is simple, auto is more difficult. auto: if I have a matrix, I could rescale such that its mesh width is larger than the largest vector. Same fo a vector of input data. But what if I don’t know whether it’s a vector or matrix? ~> second run. ~> after the first, it should be possible to autocomplete the mesh rows/cols. Try it. If that works, we have a matrix. ~> could be done from within the scanlinelength routines: auto-detect mesh/rows mesh/cols mesh/ordering mesh/width but that fails if there is no scanline marker.
- what with log plots? What with other axis features like symbolic trafos? ~> need difference type!
- that is: quiver plots in log coords are *multiplicative* and invoke the same routines. make special handling for ‘0’.
- allow feature where (u,v) are *coords*, not vectors. this could allow additive log quiver plots.

pgfplotstodo.tex:5812 **Feature Proposal** [open, Priority 5, Epic ‘]
plot expression: make the sampling parameters available within survey phase

pgfplotstodo.tex:5816 **Feature Proposal** [open, Priority 5, Epic ‘]
the table package uses a lot of logs – but it can’t change the log basis.

pgfplotstodo.tex:5821 **Feature Proposal** [open, Priority 5, Epic ‘]
3D + axis line variants: someone might prefer GRID LINES as for the boxed case combined with axis line=left...

pgfplotstodo.tex:5865 **Feature Proposal** [open, Priority 5, Epic ‘]
Mail by Hubertus Bromberger:

- ✓Period in legend, without the need of using the math environment?
`\legend{ML spcm$. $, CW spcm$. $, ML AC};`
- Maybe a more straight forward way for legend to implement something like shown in the graph. (see his mail .tex) ~> plot marks only at specific points. thus, the legend image should contain both lines and marks, but there are effectively two addplot commands.
- As a physicist, I often have the problem to fit curves. A job gnuplot can do very well. It should be possible using "raw gnuplot" but maybe you can either provide an example or even implement a more straight forward way for this purpose.
- The color scheme is not really my taste. In CONTEXT:

```

cycle list={%
{Col1,mark=*},
{Col2,mark=square*},
{Col3,mark=diamond*},
{Col4,mark=star},
{Col5,mark=pentagon*},
{Col6,mark=square*},
{Col7,mark=diamond*},
{Col8,mark=triangle* }}
\definecolor [Col1] [r=0.24106,g=0.05490,b=0.90588] % blau
\definecolor [Col2] [r=1,g=0.05490,b=0.06667] % rot
\definecolor [Col3] [r=0.65490,g=0.73333,b=0.01176] % grn
\definecolor [Col4] [r=0.08627,g=0.92549,b=0.91373] % tyrkis
\definecolor [Col5] [r=1,g=0.5,b=0] % orange
\definecolor [Col6] [r=0.54118,g=0.51765,b=0.51765] % grau
\definecolor [Col7] [r=0.80784,g=0.49804,b=0.06275] % okker
\definecolor [Col8] [r=0.74902,g=0.07451,b=0.91765] % lila

```

- Sometimes it would be good to have a bit more of a programming language, but still that's not what tex is made for. The python-script looks promising, it's just, that I think it doesn't work with context.

pgfplotstodo.tex:5874 **Feature Proposal** [open, Priority 5, Epic ‘']
add something like

```
\pgfplotstabletypeset[
  cell { 1 }{ 2 }={\multirow{*}{3}{text}}
]
```

pgfplotstodo.tex:5918 **Feature Proposal** [open, Priority 5, Epic ‘']
ternary diagrams todo:

- the `\pgfplotsqpointoutsideofaxis` work only for position 1, nothing in-between (since it doesn't compute the other axis components correctly)
- data ranges are currently only correct if in $[0,1]$ or if one provides the `[xyz]min` and `[xyz]max` keys (and the ternary limits `relative=false`). How should it work!?

pgfplotstodo.tex:5935 **Feature Proposal** [open, Priority 5, Epic ‘']
contour:

- `labels=true,false,auto` \rightsquigarrow auto should deactivate labels if there are too many contour lines.
- labels should not be clipped...
- add label position shifting facilities. \rightsquigarrow identify by contour label `*and*` an optional index. There may be more than one line.

pgfplotstodo.tex:5941 **Feature Proposal** [open, Priority 5, Epic ‘']
filled contour plots (prototype is 10% ready)

works by means of gnuplot if the outer region is extended artificially. However, color data needs to be compensated etc.

pgfplotstodo.tex:5950

Feature Proposal [open, Priority 5, Epic ‘]

DUPLICATE contourf: I guess filled contour plots could be possible if always two adjacent color levels are combined into a single path which is then filled with the simplified even/odd rule (not the winding fill rule). With the underlying smoothness assumption C^0 , there can't be any level between two adjacent ones, and there can't be self-intersections.

pgfplotstodo.tex:5955

Feature Proposal [open, Priority 5, Epic ‘]

it would be very interesting to allow more flexible handling of empty lines in input data, especially files.

pgfplotstodo.tex:5974

Feature Proposal [open, Priority 5, Epic ‘]

contour draft TODO:

- color of text nodes
- make sure there is at least one label node
- implement contourf
 - often: use 'even odd rule' to fill adjacent contours.
 - but this works only if adjacent contours are contained in each other.
 - if that's not the case, perhaps I need to add an artificial path from the data limits.
 - idea: in case I know the corner values, I'd know which contour plateau requires the artificial path.
 - other idea: I could implement some sort of even-odd rule in TeX. This should also yield the information.

pgfplotstodo.tex:5980

Feature Proposal [open, Priority 5, Epic ‘]

implement simplified constructions to access DIFFERENCE coordinates. For example, `\draw ellipse` needs x radius and y radius.

pgfplotstodo.tex:6001

Feature Proposal [open, Priority 5, Epic ‘]

the 'table/y index' should be changed. It should be $\min(\text{numcols}, 1)$ instead of 1.

pgfplotstodo.tex:6012

Feature Proposal [open, Priority 5, Epic ‘]

table package and axes should improve their communication. Namely:

-
- communicate table names.
- communicate xmode/ymode
- communicate log basis [xy]

pgfplotstodo.tex:6017

Feature Proposal [open, Priority 5, Epic ‘]

provide and document access to (sanitized?) mesh/rows and mesh/cols fields during the survey phase. This might allow 2d key filters

pgfplotstodo.tex:6024

Feature Proposal [open, Priority 5, Epic ‘]

Praktisch fände ich, wenn man folgende Dinge spezifizieren kann: 1. Welche Zeilen aus der Datei ausgelesen sollen (häufig gibt es nicht nur 1, sondern mehrere Header-Zeilen, oder auch am Ende noch sonstige Zeilen)

pgfplotstodo.tex:6051

Feature Proposal [open, Priority 5, Epic ‘]

improve support for multiple ordinates

1.

```
* \pgfplotsset{set layers}
* scale only axis
* xmin=..., xmax=...,
* axis y line*=left
* axis y line*=right
* axis x line=none
```

would be hidden in the doubleaxis definition,

2. the first addplot would be the left one and the second, the right one, (???)
3. the comma separated list in the legend command's argument applies successively to the two addplot.
4. the colours of the two plots are given by the color cycle list.

pgfplotstodo.tex:6064

Feature Proposal [open, Priority 5, Epic ‘]

it would be useful if the clipping could be disabled for certain parts of the axis. Is that possible?

- yes. Idea: start clipping for every axis element separately! Shouldn't be much more expensive than a single marker path.
- should work in the same way as before, there is no difference!
- scopes should introduce no further problems
- I could eliminate the nasty marker list

pgfplotstodo.tex:6069

Feature Proposal [open, Priority 5, Epic ‘]

provide a `\pgfplotspathcube` command as generalization from the cube marker. The cube command should work similar to `pathrectangle` or `rectanglecorners`.

pgfplotstodo.tex:6079

Feature Proposal [open, Priority 5, Epic ‘]

re-implement sampling loops. I should discard the compatibility with `foreach` internally in order to gain accuracy! Maybe it is necessary to invoke different loops - one for `tikz foreach` (samples at) and one "standard" sampling routine.

todo : activate

`pgfplotsforeachgroupeduniform@loop@mathengine@PRECISE@CURRENTLY@UNUSED@`

pgfplotstodo.tex:6122

Feature Proposal [open, Priority 5, Epic ‘]

optimization ideas:

- replace `\pgfpointscale` with a 'q' version \rightsquigarrow it invokes the expensive math parser.
- `pgfmultipartnode` evaluates every anchor twice
- implement a cache for expensive, repeated math operations like 'view' directions or common results of $1/||e_i||$.
- search for unnecessary math parser invocations; replace with 'q' versions if possible.
- implement a hierarchical generalization of the 'applist' container (a tree applist of arbitrary length)
- eliminate the deprecated 'non-legend-option' processing.
- remove the different (empty) paths of the axis node – it appears they are not necessary and waste only time and mem.

- try implementing an abstract 'serialize' and 'unserialize' method - it might be faster to re-process input streams instead of generating preprocessed coordinate lists.
- try to reduce invocations of pgfkeys
- optimize the filtered pgfkeys invocations - the filter is slower than necessary!
- the plot mark code invokes a lot of math parsing routines - which is a waste of time in my opinion. All expressions etc. have already been parsed.
- the point meta transform is set up twice for scatter plots.
- my elementary data structures always use `\string` to support macros as data structure names. I fear this might be ineffective. Perhaps its better to check if the argument is a macro (at creation time, thus only once) and call `\edef#1{\string#1}` to assign some sort of name to it. This will invoke `\string` only once. Is this faster?
- eliminate the 'veclength' invocations for single axes - they can be replaced with "inverse unit length * (max-min)"
- the key setting things can be optimized with pgfkeysdef
- create the /pgfplots/.unknown handler (.search also=/tikz) once and remember it.
- the (new) tick label code might be very expensive:
 - check for (unnecessary) calls to `\pgfpointnormalised` – the normal vectors are already normalised!
 - check the cost for bounding box size control of the tick labels – maybe this can be optimized away if it is not used. But this decision is not easy.

pgfplotstodo.tex:6127

Feature Proposal [open, Priority 5, Epic “]

perhaps math style

`{grid=major, axis x line=middle, axis y line=center, tick align=outside}`

pgfplotstodo.tex:6136

Feature Proposal [open, Priority 5, Epic “]

provide access to axis limits and data bounding box. It would be useful to get access to axis coordinates, for example in 'circle (XXX)'

pgfplotstodo.tex:6141

Feature Proposal [open, Priority 5, Epic “]

allow math expressions for axis limits etc. Idea: try float parsing routine; if it fails: use math parser first.

pgfplotstodo.tex:6148

Feature Proposal [open, Priority 5, Epic ‘’]

write a public math interface which provides access to axis internals like limits, the ‘dimen-to-coordinate’ method and so on. \rightsquigarrow it might be useful to use pgfmathparse for any numerical input argument as well.

pgfplotstodo.tex:6184

Feature Proposal [open, Priority 5, Epic ‘’]

Store the axis limits into the axis’ node as saved macros. This would allow

- ‘use [xy] limits of= \langle axis name \rangle ’
- access to axis limits from other macros.
- provide a command `\pgfplotslimits{current axis}{x}{min}` which expands to the ‘xmin’ limit. PROBLEM: to WHICH limit: the untransformed one? The transformed one? The logarithmized one?
 - \langle I can’t compute $\exp(xmin)$ in log plots!
 - Ideas:
 - provide both, if possible. It is NOT possible for log axes.
 - use log-limits (possibly combined with ‘logxmin=’ option ?)
 - The operation requires several operations because floats need to be converted. Idea: do that only for NAMED AXES.
 - all user-interface macros must be expandable!
 - I don’t want to spent time for number format conversions unnecessarily here!
 - provide `\pgfplotslimits` and `\pgfplotstransformedlimits` combined with simpler key-value interfaces
 - I could also provide access to the unit lengths (they are available as macro anyway)
 - ALTERNATIVE: implement access to axis limits as a math function which simply defines `\pgfmathresult`.
 - that is probably the most efficient way to do it. I only need to register the new function(s) to PGF MATH.
 - PGF 2.00: use `\csname pgfmath@parsefunction@\pgfmath@parsedfunctionname\endcsname`
 - PGF \langle 2.00: use `\pgfmathdeclarefunction` Is it possible to provide ‘string’ arguments which are not parsed? No.

pgfplotstodo.tex:6190

Feature Proposal [open, Priority 5, Epic ‘’]

I could provide public macros for the data transformations (and inverse transformations). This would also allow relatively simple access to axis limits.

- pgfplotstodo.tex:6194 **Feature Proposal** [open, Priority 5, Epic ‘] cycle list should be implemented using an array structure. That’s faster.
- pgfplotstodo.tex:6200 **Feature Proposal** [open, Priority 5, Epic ‘] what about a feature like ‘draw[xmin=...,xmax=...] fitline between points (a) (b)’?
- pgfplotstodo.tex:6204 **Feature Proposal** [open, Priority 5, Epic ‘] interpolate missing coordinates for stacked plots.
- pgfplotstodo.tex:6210 **Feature Proposal** [open, Priority 5, Epic ‘] the error bar implementation is relatively inefficient. Think about something like ‘pgfplots/error bars/prepare drawing’ which sets common style keys for every error bar
- pgfplotstodo.tex:6240 **Feature Proposal** [open, Priority 5, Epic ‘] think about using a combination of the visualization engine of pgf CVS and my prepared-list-structure. Maybe I can adjust the list format for the current plot type? I need
- scatter/line plots 2D
 - meta coords
 - quiver may need extra vectors
 - matrix plots may need twodimensional structure
 - error bars could be handled more consistently
 - ...
 - $\hat{}$ implement a visualization class which provides methods
 - prepare()
 - visualize()
 - serialize()
 - visualizestream() and provide protected pgfplots methods
 - axis \rightsquigarrow preprocesscoordinate (filters, logs)
 - visualizer \rightsquigarrow prepare()
 - axis \rightsquigarrow processcoordinate()
 - visualizer \rightsquigarrow serialize()

- axis \rightsquigarrow postprocesscoordinate() The markers as they are implemented now don't really fit into this framework. The clipping region is not really what I want here... Idea: enable/disable clipping separately for each drawing command!

pgfplotstodo.tex:6244

Feature Proposal [open, Priority 5, Epic ‘’]

the coordindex shouldn't be changed by z buffer=sort

pgfplotstodo.tex:6277

Feature Proposal [open, Priority 5, Epic ‘’]

table package: provide abstract layer for low level storage interface. Idea: the interface should allow the container interface

- push_back()
- get(i)
- set(i)
- foreach()
- pop_front()
- newempty()
- clone()
- unscope()
- startPushBackSequence()
- stopPushBackSequence()

\rightsquigarrow this could allow to use arrays for fast algorithms. At least it would make things easier to read. Problem as always: the 'unscope()' operation. Currently, I have two different structures: the applists which have fast construction properties and the standard lists which implement the rest. Can I combine both? Yes, by means of the incremental construction pattern:

```

\startPushBackSequence
\push_back
\push_back
\push_back
\stopPushBackSequence

```

\rightsquigarrow inside of the construction, only `\push_back` is allowed and the structure is in "locked state" (low level: applist repr) \rightsquigarrow Idea: the creation is fast, afterwards, it has flexibility.

pgfplotstodo.tex:6333 **Feature Proposal** [open, Priority 5, Epic ‘] support `\multicolumn` for legends

pgfplotstodo.tex:6338 **Feature Proposal** [open, Priority 5, Epic ‘] it appears line breaks in legend descriptions are a problem (?) \rightsquigarrow bug in pgf: `\\` is overwritten and won't be restored.

pgfplotstodo.tex:6346 **Feature Proposal** [open, Priority 5, Epic ‘] pgfplotstable file open protocol: provide public listener interface

pgfplotstodo.tex:6350 **Feature Proposal** [open, Priority 5, Epic ‘] `\addplot coordinates {\macro};`

pgfplotstodo.tex:6374 **Feature Proposal** [open, Priority 5, Epic ‘] precise width calculation idea:

- Problem: total width depends on width of axis descriptions
- width of axis descriptions depends on position of axis descriptions
- position of axis descriptions depends on width of axis
- width of axis depends on width of axis descriptions
- non-linearly coupled system.
- Idea: introduce a loop.
 - details:
 1. place axis descriptions + the axis rectangle into a box.
 2. Measure box's width, throw it away if it is too bad. Keep it and stop iteration otherwise.
 3. recompute the complete scaling.
 4. go back to step 1.) and iterate
 - one or two iterations should be enough .
 - it's not necessary to recompute the prepared and stored plots. Just keep them in main memory until the scaling is fixed.

pgfplotstodo.tex:4955

Feature Proposal [open, Priority 4, Epic ‘]

regression line computation: also generate macros containing the coefficient of determination

http://en.wikipedia.org/wiki/Coefficient_of_determination

<https://tex.stackexchange.com/questions/147249/pgfplots-linear-regression-mean-square-error>

pgfplotstodo.tex:4926

Feature Proposal [open, Priority 3, Epic ‘]

add support for symlogs <http://stackoverflow.com/questions/3305865/what-is-the-difference-between-log-and-symlog>

pgfplotstodo.tex:5627

Feature Proposal [open, Priority 3, Epic ‘Performance’]

disable bounding box updated during addplot – it makes no sense and wastes time (unless the axis is hidden)

pgfplotstodo.tex:4922

Feature Proposal [open, Priority 2, Epic ‘]

faceted allows to draw the entire rectangle.

It would allow cool effects if one could draw only those lines along the x direction (or y direction).

Compare <http://tex.stackexchange.com/questions/166768/draw-a-surface-from-scattered-curves>

pgfplotstodo.tex:4941

Feature Proposal [open, Priority 1, Epic ‘]

Optimization: if the same plot contains `name intersections` and `fill between` or `intersection segments`: compute the intersection points just once

pgfplotstodo.tex:5465

Feature Proposal [open, Priority 1, Epic ‘]

nested axes would be a nice feature. TODO: - update the list of global state variables - "interrupt" these variables somehow. - make sure local redefinitions of TikZ commands (like point commands) work; the `\let...@orig=` assignments should be handled somehow. - What about keys? They will be inherited from the outer axis... perhaps the best would be an

```
\endgroup
<nested axis>
\begingroup
<restore state>
```

which includes the keys of the outer axis!?

pgfplotstodo.tex:5489 **Feature Proposal** [open, Priority 1, Epic ‘]

log plots: minor tick num would be useful here! If tick labels are placed at '1e-5, 1e0', minor tick num= 4 would lead to the minor tick lines at '1e-4,1e-3,1e-2,1e-1' which is useful. So:allow minor tick num for log axes. ~> need to adjust the check for "uniform log ticks"

pgfplotstodo.tex:5923 **Feature Proposal** [cancelled, Priority 5, Epic ‘]

idea: 'mesh/ordering=auto'. Just check for 'x varies' and 'y varies'! The two first points inside of a scanline are enough.